

OFFICER IN CHARGE OF CONSTRUCTION  
PACIFIC DIVISION  
NAVAL FACILITIES ENGINEERING  
COMMAND DETACHMENT, FAR EAST

NAVFAC  
SPECIFICATION  
NO. 42-03-0178

Construction Contract No.  
N62836-03-C-0178  
WO No. BPSLZ  
PE: 421 H.H.

REPLACE SIDING, NEGISHI

for the

HOUSING ACTIVITY CIVIL ENGINEER,  
COMMANDER U.S. NAVAL FORCE, JAPAN

SPECIFICATION AND DRAWINGS PREPARED BY:

PUBLIC WORKS CENTER, JAPAN  
DESIGN & ENGINEERING DEPARTMENT

PE/PDE:	DATE	MECH:	DATE
<i>H. Hatai</i>	<i>7/9/03</i>	<i>M. Hatai</i>	<i>7/9/03</i>
SPEC:	DATE	ELECT:	DATE
<i>M. Tanaka</i>	<i>9 Jul 03</i>	<i>N. Hatai</i>	<i>7/9/03</i>
ARCH:	DATE	CIVIL:	DATE
<i>K. Suget</i>	<i>7/9/03</i>		
STRUCT:	DATE	FIRE PROT:	DATE
DSGN DIR:	DATE		
<i>S.A. KOEPSELE</i>	<i>7/9/03</i>		
SUBMITTED BY	DATE		
<i>K. MATSUZAKI</i>	<i>7/9/03</i>		
FUNCTIONAL APPROVAL	DATE		
<i>[Signature]</i>	<i>24 July 2003</i>		
APPROVED BY	DATE		
COMMANDER NAVFAC	<i>/ /</i>		

ARCHITECT/ENGINEER'S  
SEAL

## CONTENTS

### DIVISION 1    GENERAL REQUIREMENTS

Section 01010    General Paragraphs  
Section 01330    Submittal Procedures  
Section 01450    Quality Control  
Section 01525    Safety Requirements  
Section 01560    Environmental Protection  
Section 01801    Safety Requirements for Crane Operation

### DIVISION 2    SITE WORK

Section 02220    Site Demolition

### DIVISION 6    WOOD AND PLASTICS

Section 06200    Rough and Finish Carpentry

### DIVISION 7    THERMAL AND MOISTURE PROTECTION

Section 07311    Asphalt Shingles  
Section 07600    Gutter and Downspout  
Section 07920    Sealant

### DIVISION 9    FINISHES

Section 09250    Cement Board Siding  
Section 09900    Paints and Coatings

### DIVISION 13   SPECIAL CONSTRUCTION

Section 13283    Removal and Disposal of Lead-containing Paint

### DIVISION 16   ELECTRICAL

Section 16050    Basic Electrical Materials and Methods  
Section 16402    Electrical Distribution System

## DIVISION 1

### GENERAL REQUIREMENTS

#### SECTION 01010

##### GENERAL PARAGRAPHS

#### PART 1 - GENERAL

1.1 GENERAL INTENTION: It is the declared and acknowledged intention and meaning to provide and secure "REPLACE SIDING, NEGISHI", complete and ready for use.

1.2 GENERAL DESCRIPTION: The work includes siding replacement and related works, as described on plans and specifications. Existing material known to contain lead-based paint will be encountered. The Contractor shall remove the lead-based paint as specified in Section 13283, "Removal and Disposal of Lead-containing Paint".

1.3 LOCATION: The work shall be located at the Negishi Dependent Housing Area, Japan, approximately as shown. The exact location will be indicated by the Contracting Officer.

#### 1.4 PROJECT SCHEDULE AND TIME CONSTRAINTS:

1.4.1 Commencement and Completion of Work: The Contractor shall be required to complete the entire work, ready for use, not later than 150 calendar days including the mailing period after the date of Award. The mailing period includes the days for mailing of the Notice of Award and the submission of the required bonds and Certificate of Insurance. The time for completion shall include final clean-up of the premises. The Contractor shall complete the on-site work of one(1) building within 50 calendar days and complete all the on-site work within 120 calendar days.

a. Working Hours: The project site will be available when work is being performed on site and during regular working hours established by the Resident Officer in Charge of Construction(ROICC) between 8:00 a.m. and 4:45 p.m., Monday through Friday, excluding all U.S. legal holidays.

b. Work Outside Regular Hours: The Contracting Officer or authorized representative, may approve work outside regular hours. If

the Contractor desires to carry on work outside regular hours, including Saturdays, Sundays, and Government holidays, submit a written justification giving the benefit to the Government, specific dates, hours, location, type of work to be performed, contract number and project title for approval, and submit request outside regular hours 96 hours in advance of the date the work will start. During periods of darkness, light the different parts of the work in an approved manner. All work outside of regular hours is subject to approval by the Contracting Officer. All work outside of regular hours shall be able to demonstrate a benefit to the Government.

#### 1.5 GOVERNMENT REPRESENTATIVES:

a. The work will be under the general direction of an officer of the Civil Engineer Corps, United States Navy, or another officer or representative of the Government, designated in block 26 of Standard Form 1442. Except in connection with the Disputes Clause of this contract, this designated person has complete charge of and exercises full supervision over the work so far as it affects the interests of the Government.

b. For the purposes of the Disputes Clause, the "Contracting Officer" is the Commander, Naval Facilities Engineering Command, or his representatives warranted for this purpose. Any claim submitted under the Disputes Clause shall be submitted to the Contracting Officer in care of the person designated in block 26 of Standard Form 1442 as the representative of the Contracting Officer authorized to receive the claim.

c. The provisions of this paragraph or provisions elsewhere in this contract regarding supervision, approval, or direction by the Contracting Officer or the designated person shall not relieve the Contractor of responsibility for accomplishing the work, with regard to sufficiency or time of performance, except as otherwise provided.

1.6 ORAL MODIFICATION: No oral statement by any person other than the Contracting Officer or authorized representative, as provided in the Contract Clause entitled "Changes" will have authority to modify or otherwise affect the terms of this contract.

#### 1.7 INSURANCE:

1.7.1 Minimum Requirements: The Contractor shall procure and maintain during the entire period of performance under this contract the following minimum insurance coverage:

### Type of Insurance

- a. Comprehensive General Liability: ¥50,000,000 per occurrence.
- b. Automobile Liability: ¥20,000,000 per person, ¥50,000,000 per occurrence, ¥2,000,000 per occurrence for property damage.
- c. Workers' Compensation: As required by Japanese workers' compensation and occupational disease statutes.
- d. Other as required by Japanese law.

1.8 NO WAIVER BY THE GOVERNMENT: The failure of the Government in one or more instances to insist upon strict performance to terms of this contract or to exercise an option herein conferred shall not be construed as a waiver or relinquishment of the right to assert or rely upon such terms or option on a future occasion.

### 1.9 SUBMITTALS:

1.9.1 Administrative or Closeout Submittals: Submit all of the following submittals, except "As-built drawings" and "Request for Information(RFI)", at one time.

- a. Schedule of prices
- b. As-built drawings
- c. Subcontractors and personnel list
- d. Vehicle list
- e. Construction schedule
- f. Request for information (RFI)

#### 1.9.1.1 Schedule of Prices:

a. Data Required: Within 15 calendar days after the date of Award, the Contractor shall prepare and submit to the ROICC five(5) copies of the Schedule of Prices (construction contract) on the forms furnished for this purpose. The schedule of prices shall consist of a detailed breakdown of the contract price, giving the quantities for each of the various kinds of work; the unit prices; and the total prices therefore. The required schedule shall be based on the actual breakdown of the bid price. The format, content, and number of copies required will be prescribed by the ROICC and will be subject to his approval. The submission of the required data shall not otherwise affect the contract terms. Payments will not be made pursuant to the

paragraph of the GENERAL PARAGRAPHS entitled "Payment to Contractor" until the Schedule of Prices has been submitted and approved.

b. Submittal Instructions: Furnish five(5) copies of the Schedule of Prices in accordance with the paragraph entitled "Data Required." Payments will not be made pursuant to the paragraph entitled "Payments to the Contractor" until the schedule of prices has been approved.

1.9.1.2 As-built Drawings: Submit within 10 calendar days after completion of work, one set of as-built drawings to the ROICC. During the work performance, the marked-up drawings shall be kept on-site

1.9.1.3 Subcontractors and Personnel List: Within 15 calendar days after the date of Award, submit to the ROICC of the names, job titles, addresses, and telephone numbers of the key personnel of the Contractor and subcontractors for use in the event of an emergency. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.9.1.4 Vehicle List: Submit as required by the Contracting Officer.

1.9.1.5 Construction Schedule: Reference "FAR 52.236-15" for general requirements. Within 15 calendar days after the date of Award, the Contractor shall submit a detailed construction schedule by using CPM "critical path method" for acceptance prior to starting work. Interim schedules, not to exceed 15 calendar days may be accepted depending on the circumstances of the project. The schedule shall be in the form of a computer generated project chart(CPM) utilizing commercially available software specifically for project scheduling. The construction schedule shall include the following at a minimum:

- a. Times projected for all salient, major features of work.
- b. Times for critical submittals, approvals, and procurements of materials and equipment.
- c. Times for testing and inspections.
- d. Primary and secondary/alternate dates the Contractor intends to hold preparatory meetings for each definable feature work.

The project schedule shall be updated monthly or upon approval of significant modifications to the contract that impact existing work. All changes to the schedule must be approved prior to implementing.

1.9.1.6 Request for Information (RFI): When the Contractor has questions, submit with sample figure attached as ATTACHMENT-1 at the end of this section.

1.10 PAYMENTS TO THE CONTRACTOR: In compliance with the Contract Clause entitled "Payments Under Fixed-Price Construction Contract," payments will be made upon submission of itemized requests by the Contractor and will be subject to reduction for overpayments or increase for underpayments on preceding payments to the Contractor.

1.10.1 Obligation of Government Payments: The obligation of the Government to make payments required under provisions of this contract shall, in the discretion of the ROICC, be subject to:

a. Reasonable deductions on account of defects in material or workmanship; and

b. Claims which the Government may have against the Contractor under or in connection with this contract.

1.11 CONTRACTOR'S INVOICE AND CONTRACT PERFORMANCE STATEMENT: Requests for payment in accordance with the terms of the contract shall consist of:

a. The Contractor's invoice on the form furnished for this purpose, which shall show, in summary form, the basis for arriving at the amount of the invoice.

b. The contract performance statement on the form which shows in detail the estimated cost percentage of completion and value of completed performance for each of the activities. The Contracting Officer will prescribe the format, content, and number of copies required. The submission of the required data will not otherwise affect the contract terms.

c. Updated schedule with each invoice showing actual progress vs. original schedule.

1.12 EQUITABLE ADJUSTMENTS - WAIVER AND RELEASE OF CLAIMS:

a. Whenever the Contractor submits a claim for equitable adjustment under a clause of this contract which provides for equitable adjustment of the contract, the claim shall include all types of adjustments in the total amounts to which the clause entitles the Contractor, including, but not limited to, adjustments arising out

of delays or disruptions or both caused by such change. Except as the parties may otherwise expressly agree, the Contractor shall be deemed to have waived: (1) adjustments to which the Contractor might otherwise be entitled under the clause where the claim fails to request adjustments; and (2) increase in the amount of equitable adjustments additional to those requested in the Contractor's claim.

b. The Contractor agrees that, if required by the ROICC, the Contractor shall execute a release, in form and substance satisfactory to the ROICC, as part of the supplemental agreement setting forth the aforesaid equitable adjustment. The Contractor further agrees that such release shall discharge the Government, including the Government's officers, agents, and employees, from further claims, including, but not limited to, further claims arising out of delays or disruptions caused by the aforesaid change.

1.13 ACTIVITY REGULATIONS: Obey activity regulations, including fire, traffic, safety, energy conservation, and security regulations. Provide written "General Authorization to Work on Base" to the Contracting Officer, via the Industrial Security Office, Commander Fleet Activities, Yokosuka. Personnel employed at the activity shall keep within the limits of the work (and avenues of ingress and egress) and shall not enter any restricted areas unless required to do so and are cleared for such entry. Wear hard hats, with the Contractor's name prominently displayed, in designated hard hat areas. The Contractor's equipment shall be conspicuously marked for identification.

1.14 ORDER OF WORK: Schedule work so as to cause the least amount of interference with activity operations. Work schedules are subject to the approval of the ROICC.

1.15 EXISTING WORK: Prevent injury or damage to existing work which remains. Repair or replace as directed, in kind and in a manner to match existing adjoining work, the portions of existing work damaged or altered during construction. Work of this nature shall be performed by the Contractor at the Contractor's expense. At the completion of operations, existing work shall be in a condition equal to or better than that which existed before the new work started.

1.16 RESTRICTIONS ON OPERATIONS:

1.16.1 Coordination With Other Work: The Contract Clause entitled "Other Contracts"; the paragraph entitled "Order of Work"; and the following apply:



1.16.1.1 Occupied Building: Work is in and around existing buildings which are occupied. Do not enter buildings without prior approval.

1.17 ACTIONS REQUIRED OF THE CONTRACTOR:

1.17.1 Activity Permits: Obtain pursuant to the paragraph of Section 01010, "General Paragraphs," entitled "Activity Regulations." Permits are required for, but are not necessarily limited to, welding, digging, and burning. Allow seven(7) calendar days for processing of the application.

1.17.2 Storm Protection: When warnings of gale force winds of 34-49 knots are issued, take precautions to minimize danger to persons, and protect the work and nearby Government property. Precautions shall include, but are not limited to, closing openings; removing loose materials, tools, and equipment from exposed locations; and removing or securing scaffolding and other temporary work.

1.17.2.1 Actions Required During Typhoon Conditions: Unless directed otherwise by the ROICC comply with the following:

a. If condition occurs at night, commence securing operations at first light of the next day. On weekends or holidays, commence securing operations at the earliest opportunity.

b. Tropical Storm/Typhoon Condition One (Sustained winds of 50 knots or greater expected within 12 hours): Secure the job site.

c. Tropical Storm/Typhoon Condition Two (Sustained winds of 50 knots or greater expected within 24 hours): Curtail or cease routine activities until securing operation is complete. Reinforce or remove form work and scaffolding. Secure machinery, tools, equipment, materials, or remove from the job site.

d. Tropical Storm/Typhoon Condition Three (Sustained winds of 50 knots or greater expected within 48 hours): Maintain "Condition Four" requirements and commence securing operations necessary for "Condition One" which cannot be completed within 18 hours.

e. Typhoon Condition Four (Sustained winds of 50 knots or greater expected within 72 hours): Normal daily job site cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at

the close of each work day. Maintain the construction site, including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than 4 feet high.

1.18 SANITATION: Provide adequate sanitary conveniences of a type approved for the use of persons employed on the work, properly secluded from public observation, and maintained as directed. Upon completion of the work, remove the conveniences from the premises, leaving the premises clean and free from nuisance.

1.19 SPECIFICATIONS AND STANDARDS: The specifications and standards referenced in this project specification, including addenda, amendments, and errata listed, will govern in all cases where references thereto are made. In case of differences between these specifications or standards and this project specification or its accompanying drawings, this project specification and its accompanying drawings will govern to the extent of such differences. Otherwise, the referenced specifications and standards will apply. The requirement for packaging, packing, marking, and preparation for shipment or delivery included in the referenced specifications will apply only to materials and equipment that are furnished directly to the Government and not to materials and equipment that are to be furnished and installed by the Contractor.

1.20 OPTIONAL REQUIREMENTS: Where a choice of materials or methods, or both, is permitted in this contract, the Contractor will be given the right to exercise the option unless otherwise required by the specification.

#### 1.21 FACILITIES AND SERVICES

1.21.1 Availability of Utilities Services: Pursuant to the Contract Clauses entitled "Availability and Use of Utilities Services," reasonable amounts of the following utilities will be made available to the Contractor at no cost, except the utilities for the Contractor's temporary office and hut at the following rates:

Electricity:	\$136.48 per 1,000 KWH
Potable Water:	\$ 10.36 per 1,000 Gal

Rates shown were the latest available during the preparation of this specification, and are provided for informational purposes only. The point at which the Government will deliver such utilities or services and the quantity available is to be directed by the Contracting Officer. Pay costs incurred in connecting, disconnecting

converting, and transferring the utilities to the work. The Contractor shall furnish backflow-preventing devices on connections to domestic water lines; meters; transformers; necessary accessories and perform necessary excavation/backfilling. The Contractor shall make connections and disconnections.

#### 1.22 CONCILIATION CLAUSE:

a. Any disagreement arising under this contract which is not resolved by the parties to this contract may be submitted to the U.S.-Japan Joint Committee for Conciliation in accordance with paragraph 10, Article XVIII, of the Status of Forces Agreement under Article VI, of the Treaty of Mutual Cooperation and Security between Japan and the United States of America.

b. Recourse to the Joint Committee for Conciliation for resolving disputes is available in addition to the procedures set forth in the Contract Disputes Act of 1978 and the Disputes Clause of this contract, 52.233-1. A request for conciliation by the Joint Committee, however, shall not toll the time periods allowed under the Contract Disputes Act for appealing the Contracting Officer's final decision to either the Armed Services Board of Contract Appeals or U.S. Court of Federal Claims.

c. Upon filing a request for conciliation with the Joint Committee, the Contractor shall immediately notify the Contracting Officer in writing of the request.

#### 1.23 WARRANTY:

1.23.1 Pre-Warranty Conference: Prior to contract completion and at a time designated by the Contracting Officer, the Contractor shall meet with the Contracting Officer to develop a mutual understanding with respect to the requirements of this clause. Communication procedures for Contractor notification of warranty defects, priorities with respect to the type of defect, reasonable time required for Contractor response, and other details deemed necessary by the Contracting Officer for the execution of the construction warranty shall be reviewed at this meeting.

##### 1.23.2 Equipment Warranty Identification Tags:

1.23.2.1 The Contractor shall provide warranty identification tags on all Contractor furnished equipment which he has installed.

a. The tags shall be similar in format and size to the exhibits provided by this specification, they shall be suitable for interior and exterior locations, resistant to solvents, abrasion, and to fading caused by sunlight, precipitation, etc. These tags shall have a permanent pressure-sensitive adhesive back, and they shall be installed in a position that is easily (or most easily) noticeable. Contractor furnished equipment that has differing warranties on its components will have each component tagged.

b. Sample tags shall be submitted for Government review and approval. These tags shall be filled out representative of how the Contractor will complete all other tags.

c. Tags for Warrantied Equipment: The tag for this equipment shall be similar to the following. Exact format and size will be as approved.

---

EQUIPMENT WARRANTY  
CONTRACTOR FURNISHED EQUIPMENT

MFG	MODEL NO.
SERIAL NO.	
CONTRACT NO.	
CONTRACTOR NAME	
CONTRACTOR WARRANTY EXPIRES	
MFG WARRANTY(IES) EXPIRE	

---

d. If the manufacturer's name (MFG), model number and serial number are on the manufacturer's equipment data plate and this data plate is easily found and fully legible, this information need not be duplicated on the equipment warranty tag. The Contractor warranty expires (warranty expiration date) and the final manufacturer's warranty expiration date will be determined as specified in the contract.

1.23.2.2 Execution. The Contractor will complete the required information on each tag and install these tags on the equipment by the time of and as a condition of final acceptance of the equipment.

1.23.2.3 Equipment Warranty Tag Replacement. As stated in Contract Clause: WARRANTY OF CONSTRUCTION, the Contractor's warranty with respect to work repaired or replaced shall run for one year from the date of repair or replacement. Such activity shall include an updated warranty identification tag on the repaired or replaced equipment.

The tag shall be furnished and installed by the Contractor, and shall be identical to the original tag, except that the Contractor's warranty expiration date will be one year from the date of acceptance of the repair or replacement.

1.24 INTERPRETER: The Contractor shall furnish the service of an interpreter on the job. This interpreter shall have strong knowledge of the English language in terms of writing, listening, speaking and reading skills. Interpreter's English skills shall also be well suited to the construction industry. If at any time the Contracting Officer feels the Contractor's interpreter is unable to perform the duties required of him/her, the Contracting Officer will ask for his immediate replacement. When the QC manager or the project superintendent talks with the Government representative, on-site or off-site, they shall be accompanied by their interpreter.

## PART 2 - EXECUTION

2.1 CONTRACTOR'S FACILITY: If there is adequate land area available, and on the basis of non-interference in the requirements of the Government, the Contractor may be permitted to erect a structure of reasonable size at or near the site of the work or at the other location on base as directed by the Contracting Officer. The Contractor shall receive CNFJ approval for temporary facilities at Ikego area. The Government is under no obligation to provide such land, but the Contracting Officer will accept a written request for temporary assignment of an area for such use. If approved, the Contractor may proceed, providing that it is clearly understood that the Government will bear no responsibility for the safety and security of the structure or its contents (including equipment, material or any other things of whatever nature). If the Contractor erects a structure on Government controlled land in accordance with the foregoing, it shall at all times be kept in a neat, clean, orderly condition in order to improve safety and reduce fire hazards. The disposal of trash and debris shall be the Contractor's responsibility. Electric power, water, and telephone may be installed in the structure, subject to approval of the Government, on payment by the Contractor of the established charges unless otherwise specified. Within 15 calendar days after completion of this project, the Contractor shall remove the temporary facilities for this project to restore the land to the original condition.

PART 3 - TECHNICAL

3.1 PROJECT INFORMATION:

3.1.1 Contract Drawings and Specification: As specified in Contract Clause, DFARS 252.236-7001.

a. Index of Contract Drawings:

<u>NAVFAC DRAWING NO.</u>	<u>TITLE</u>
7838461	General Description of Work, Notes, Legend, Abbreviations, Symbols and Finish Schedules
7838462	Location Map and Schedule List
7838463	Plans and Elevations
7838464	Plans and Elevations
7838465	Plans and Elevations
7838466	Plan and Elevations
7838467	Plans and Elevations
7838468	Plan and Elevations
7838469	Plans and Elevations
7838470	Typical Sections
7838471	Typical Details (1)
7838472	Typical Details (2)
7838473	Scope of Work & Elec Material List
7838474	Typ Elevation
7838475	Typ Detail

\*\*\* END OF SECTION \*\*\*

<b>CONTRACT NUMBER</b>  N       -       -       -	<b>REQUEST FOR INFORMATION</b>	<b>RFI NUMBER</b>
CONTRACT TITLE:		
PRIME CONTRACTOR:		
SUBCONTRACTOR/SUPPLIER:		
TITLE OF RFI:		
CONTRACT DOCUMENTS AFFECTED BY THIS RFI (DRAWINGS, DETAILS, SPECS, ETC):		
COST EFFECT:		RESPONSE REQUESTED BY:
<b>INFORMATION REQUESTED:</b>		
_____ DATE	_____ SUBCONTRACTOR/SUPPLIER	_____ DATE
<b>ANSWER PROVIDED BY ROICC:</b>		
_____ DATE	_____ CONREP SIGNATURE	_____ DATE
_____ AROICC/AREICC SIGNATURE		
THE RFI SYSTEM IS INTENDED TO PROVIDE AN EFFICIENT AND FORMAL MECHANISM FOR RESPONDING TO CONTRACTOR'S REQUESTS FOR INFORMATION. IT IS NOT AN AUTHORITY TO PROCEED WITH ADDITIONAL WORK. IF YOU CONSIDER THE RFI RESPONSE A CHANGED CONDITION, WRITTEN NOTICE TO THE ROICC IS REQUIRED IN ACCORDANCE WITH CONTRACT PROVISIONS.		

## SECTION 01330

### SUBMITTAL PROCEDURES

#### PART 1 GENERAL

##### 1.1 DEFINITIONS:

1.1.1 Submittal Shop drawings, product data, samples, and administrative submittals presented for review and approval. Contract Clauses "FAR 52.236-5, Material and Workmanship," paragraph (b) and "FAR 52.236-21, Specifications and Drawings for Construction," paragraphs (d), (e), and (f) apply to all "submittals." Every submittal shall be written in English and Japanese. Unless otherwise specified, submit to the Contracting Officer within 15 calendar days after the date of award.

1.1.2 Types of Submittals: All submittals are classified as indicated in the paragraph "Schedule of Submittal Descriptions." The submittals also are grouped as follows:

a. Shop drawings: As used in this section, drawings, schedules, diagrams, and other data prepared specifically for this Contract, by the Contractor or through the Contractor by way of a subcontractor, manufacturer, supplier, distributor, or other lower tier contractor, to illustrate a portion of the work.

b. Product data: Preprinted material such as illustrations, standard schedules, performance charts, instructions, brochures, diagrams, manufacturer's descriptive literature, catalog data, and other data to illustrate a portion of the work, but not prepared exclusively for this Contract.

c. Samples: Physical examples of products, materials, equipment, assemblies, or workmanship that are physically identical to a portion of the work, illustrating a portion of the work or establishing standards for evaluating the appearance of the finished work or both.

d. Administrative Submittals: Data presented for reviews and approval to ensure that the administrative requirements of the project are adequately met but not to ensure directly that the work is in accordance with the design concept and in compliance with the Contract documents.

1.1.3 Approving Authority: The person authorized to approve a submittal.



1.1.4 Work: As used in this section, on- and off-site construction required by the Contract documents, including labor necessary to produce the construction and materials, products, equipment, and systems incorporated or to be incorporated in such construction.

1.2 SUBMITTALS: Submit the following in accordance with the requirements of this section.

1.2.1 SD-18, Records

a. Submittal register

1.2.1.1 Submittal Register: State for each submittal the Contractor's planned submittal date. Insert dates on copies of the "Submittal Register." "Submittal Register" form is provided as ATTACHMENT-3 through ATTACHMENT-5.

1.2.1.2 Submittal Register Preparation: Prepare and maintain a submittal register. Instructions are included in paragraph titled "SUBMITTAL REGISTER INSTRUCTIONS" for use in developing the submittal register. The submittal register with columns (a), (b), (c), (d) completed, is designated the initial submittal register required as a part of the quality control plan. The remaining columns on the submittal register forms shall be completed by the Contractor. Additional details concerning the use of the submittal register will be explained at the preconstruction conference.

1.2.1.3 Submittal of Submittal Register: The Contractor shall submit his submittal register, for approval, prior to submission of other submittals or along with their initial submittal submission. And the Contractor's copy of the completed submittal register shall be submitted to the ROICC at the completion of the project as an administrative closeout submittal.

1.3 PROCEDURES FOR SUBMITTALS

1.3.1 Reviewing, Certifying, Approving Authority: The QC organization shall be responsible for reviewing and certifying that submittals are in compliance with contract requirements. The approving authority on submittals is the QC Manager unless otherwise specified for the specific submittal.

1.3.2 Constraints:

a. Submittals listed or specified in this Contract shall conform to the provisions of this section, unless explicitly stated otherwise.

b. Submittals shall be complete for each definable feature of work; components of the definable feature interrelated as a system shall be submitted at the same time.

c. When acceptability of a submittal is dependent on conditions, items, or materials included in separate subsequent submittals, the submittal will be returned without review.

d. Approval of a separate material, product, or component does not imply approval of assembly in which the item functions.

#### 1.3.3 Scheduling:

a. Coordinate scheduling, sequencing, preparing and processing of submittals with performance of the work so that work will not be delayed by submittal processing. Allow for potential requirements to resubmit.

b. Except as specified otherwise, allow a review period, beginning with receipt by the approving authority, of 15 calendar days for submittals for QC Manager approval and 15 days for submittals for Contracting Officer approval. The period of review for submittals with Contracting Officer approval begins when the Government receives the submittal from the QC organization. The period of review for each resubmittal is the same as for the initial submittal.

1.3.4 Variations: Variations from contract requirements require Government approval pursuant to Contract Clause entitled "FAR 52.236-21, Specifications and Drawings for Construction" and will be considered where advantageous to the Government. When proposing a variation, submit a written request to the Contracting Officer, with documentation of the nature and features of the variation and why the variation is desirable and beneficial to the Government. If lower cost is a benefit, also include an estimate of the cost saving. Identify the proposed variation separately and include the documentation for the proposed variation along with the required submittal for the item. When submitting a variation for approval, the Contractor certifies the following:

1.3.4.1 Variation Is Compatible: The Contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of the work.

1.3.4.2 Review Schedule Is Modified: In addition to the normal submittal review period, a period of 15 working days will be allowed for consideration by the Government of submittals with variations.

#### 1.3.5 Contractor's Responsibilities

a. Determine and verify field measurements, materials, field construction criteria; review each submittal; and check and coordinate each submittal with requirements of the work and Contract documents.

b. Transmit submittals to the QC organization in orderly sequence, in accordance with the Submittal Register, and to prevent delays in the work, delays to the Government, or delays to separate contractors.

c. Advise the Contracting Officer of variation, as required by the paragraph entitled "Variations."

d. Correct and resubmit submittal as directed by the approving authority. When resubmitting disapproved transmittals or transmittals noted for resubmittal, the Contractor shall provide a copy of that previously submitted transmittal including all reviewer comments for use by the approving authority.

e. Direct specific attention, in writing or on resubmitted submittal, to revisions not requested by the approving authority on previous submissions.

f. Furnish additional copies of submittals when requested by the Contracting Officer, to a limit of 20 copies per submittals.

g. Complete work which must be accomplished as a basis of a submittal in time to allow the submittal to occur as scheduled.

h. Ensure no work has begun until submittals for that work have been returned as "approved," or "approved as noted".

#### 1.3.6 QC Organization Responsibilities:

a. Note the date on which the submittal was received from the contractor on each submittal.

b. Review each submittal; and check and coordinate each submittal with requirements of the work and Contract documents.

c. Review submittals for conformance with project design concepts and compliance with the Contract documents.

d. Act on submittals, determining the appropriate action based on the QC organization's review of the submittal.

(1) When the QC Manager is the approving authority, take the appropriate action on the submittal from the possible actions defined in the paragraph entitled, "Actions Possible."

(2) When the Contracting Officer is the approving authority or when a variation has been proposed, forward the submittal to the Government with the certifying statement or return the submittal marked "not reviewed" or "revise and resubmit" as appropriate. The QC organization's review of the submittal determines the appropriate action.

e. Ensure that material is clearly legible.

f. Stamp each transmittal sheet of each submittal with the QC certifying statement or approving statement, except that data submitted in bound volume or on one sheet printed on two sides may be stamped on the front of the first sheet only.

(1) When the approving authority is the Contracting Officer, the QC organization will certify submittals forwarded to the Contracting Officer with the following certifying statement:

"I hereby certify that the (equipment) (material) (article) shown and marked in this submittal is that proposed to be incorporated with Contract Number N62836-03-C-0178, is in compliance with the Contract drawings and specification, can be installed in the allocated spaces, and is submitted for Government approval.

Certified by Submittal Reviewer \_\_\_\_\_, Date \_\_\_\_\_  
(Signature when applicable)

Certified by QC Manager \_\_\_\_\_, Date \_\_\_\_\_"  
(Signature)

(2) When the approving authority is the QC Manager, the QC manager will use the following approval statement when returning submittals to the Contractor as "Approved" or "Approved as Noted."

"I hereby certify that the (material) (equipment) (article) shown and marked in this submittal and proposed to be incorporated with Contract Number N62836-03-C-0178, is in compliance with the contract drawings and specification, can be installed in the allocated spaces, and is \_\_\_\_\_ approved for use.

Certified by Submittal Reviewer \_\_\_\_\_, Date \_\_\_\_\_  
(Signature when applicable)

Approved by QC Manager \_\_\_\_\_, Date \_\_\_\_\_"

(Signature)

g. Sign the certifying statement or approval statement. The person signing the certifying statements shall be the QC organization member designated in the approved QC plan. The signatures shall be in original ink with stamp. Stamped signatures are not acceptable.

h. Update the submittal register as submittal actions occur and maintain the submittal register at the project site until final acceptance of all work by the Contracting Officer.

i. Retain a copy of approved submittals at the project site, including the Contractor's copy of approved samples.

1.3.7 Government's Responsibilities: When the approving authority is the Contracting Officer, the Government will:

a. Note the date on which the submittal was received from the QC Manager, and on each submittal for which the Contracting Officer is the approving authority. The Contractor shall date stamp with time.

b. Review submittals for approval within the scheduling period specified and only for conformance with project design concepts and compliance with the Contract documents.

c. Identify returned submittals with one of the actions defined in the paragraph entitled "Actions Possible" and with markings appropriate for the action indicated.

1.3.8 Actions Possible: Submittals will be returned with one of the following notations:

a. Approved as submitted.

b. Approved except as noted on drawings. Resubmission not required.

c. Approved except as noted on drawings. Refer to attached sheet. Resubmission required.

d. Will be returned by separate correspondence.

e. Disapproved. See attached sheet.

#### 1.4 FORMAT OF SUBMITTALS

1.4.1 Transmittal Form: Transmit each submittal, except sample installations and sample panels, to the office of the approving

authority. Transmit submittals with a transmittal form (ATTACHMENT-1 and -2) prescribed by the Contracting Officer and standard for the project. The transmittal form shall identify the Contractor, indicate the date of the submittal, and include information prescribed by the transmittal form and required in the paragraph entitled "Identifying Submittals." Process transmittal forms to record actions regarding sample panels and sample installations.

1.4.2 Identifying Submittals: Identify submittals, except sample panel and sample installation, with the following information permanently adhered to or noted on each separate component of each submittal and noted on the transmittal form. Mark each copy of each submittal identically, with the following:

- a. Project title and location.
- b. Construction Contract number.
- c. The section number of the specification section by which the submittal is required.
- d. The submittal description (SD) number of each component of the submittal.
- e. When a resubmission, an alphabetic suffix on the submittal description, for example, SD-10A, to indicate the resubmission.
- f. The name, address, and telephone number of the subcontractor, supplier, manufacturer and any other second tier contractor associated with the submittal.
- g. Product identification and location in project.

1.4.3 Format for Product Data:

- a. Present product data submittals for each section as a complete, bound volume. Include a table of contents listing page and catalog item numbers for product data.
- b. Indicate, by prominent notation, each product which is being submitted; indicate the contract specification section number and paragraph number to which it pertains.
- c. Supplement product data with material prepared for the project to satisfy submittal requirements for which product data does not exist. Identify this material as developed specifically for the project.

#### 1.4.4 Format for Shop Drawings:

a. Shop drawings shall not be less than A4 (297 x 210 mm) (8 1/2 by 11 inches) nor more than AO (1189 x 841 mm) (30 x 42 inches).

b. Present A4 (297 x 210 mm) (8 1/2 x 11 inches) sized shop drawings as a part of the bound volume for the submittals required by the section. Present larger drawings in sets.

c. Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to the information required in the paragraph entitled "Identifying Submittals."

d. Dimension drawings, except diagrams and schematic drawings; prepare drawings demonstrating interface with other trades to scale. Identify materials and products for work shown.

#### 1.4.5 Format of Samples:

a. Furnish samples in the sizes below, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

(1) Sample of Equipment or Device: Full size.

(2) Sample of Materials Less Than 50 by 75 mm (2 by 3 inches): Built up to A4 (297 x 210 mm) (8 1/2 by 11 inches).

(3) Sample of Materials Exceeding A4 (297 x 210 mm) (8 1/2 by 11 inches): Cut down to A4 (297 x 210 mm) (8 1/2 by 11 inches) and adequate to indicate color, texture, and material variations.

(4) Sample of Linear Devices or Materials: 250 mm (10 inch) length or length to be supplied, if less than 250 mm (10 inches). Examples of linear devices or materials are conduit and handrails.

(5) Sample of Non-Solid Materials: Pint. Examples of non-solid materials are sand and paint.

(6) Color Selection Samples: 50 by 100 mm (2 inches by 4 inches).

(7) Sample Panel: 1200 by 1200 mm (4 by 4 feet).

(8) Sample Installation: 10 square meters (100 square feet).

b. Samples Showing Range of Variation: Where variations are unavoidable due to the nature of the materials, submit sets of samples

of not less than three units showing the extremes and middle of the range.

c. Reusable Samples: Incorporate returned samples into the work only if so specified or indicated. Incorporated samples shall be in undamaged condition at the time of use.

d. Recording of Sample Installation: Note and preserve the notation of the area constituting the sample installation but remove the notation at the final clean up of the project.

#### 1.4.6 Format of Administrative Submittals:

a. When the submittal includes a document which is to be used in the project or become a part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document, but to a separate sheet accompanying the document.

#### 1.5 QUANTITY OF SUBMITTALS:

##### 1.5.1 Number of Copies of Product Data:

a. Submit four copies of submittals of product data requiring review and approval only by the QC organization and four copies of product data requiring review and approval by the Contracting Officer.

b. Submit administrative submittals required under "SD-19, Operation and Maintenance Manuals."

1.5.2 Number of Copies of Shop Drawings: Submit shop drawings in compliance with the quantity requirements specified for product data.

##### 1.5.3 Number of Samples:

a. Submit two samples, or two sets of samples showing range of variation, of each required item. One approved sample or set of samples will be retained by the approving authority and one will be returned to the Contractor.

b. Submit one sample panel. Include components listed in technical section or as directed.

c. Submit one sample installation, where directed.

d. Submit one sample of non-solid materials.

##### 1.5.4 Number of Copies of Administrative Submittals:



a. Unless otherwise specified, submit the administrative submittals compliance with the quantity requirements specified for product data.

#### 1.6 SCHEDULE OF SUBMITTAL DESCRIPTIONS (SD):

SD-01, Data: Submittals which provide calculations, descriptions, or other documentation regarding the work.

SD-02, Manufacturer's Catalog Data: Data composed of catalog cuts, brochures, circulars, specifications and product data, and printed information in sufficient detail and scope to verify compliance with requirements of the contract documents. A type of product data.

SD-03, Manufacturer's Standard Color Charts: Preprinted illustrations displaying choices of color and finish for a material or product. A type of product data.

SD-04, Drawings: Submittals which graphically show relationship of various components of the work, schematic diagrams of systems, detail of fabrications, layout of particular elements, connections, and other relational aspects of the work. A type of shop drawing.

SD-05, Design Data: Design calculations, mix designs, analyses, or other data, written in nature and pertaining to a part of the work. A type of shop drawing.

SD-06, Instructions: Preprinted material describing installation of a product, system, or material, including special notices and Material Safety Data Sheets, if any, concerning impedances, hazards, and safety precautions. A type of product data.

SD-07, Schedules: A tabular list of data or tabular list including location, features, or other pertinent information regarding products, materials, equipment, or components to be used in the work. A type of shop drawing.

SD-08, Statements: A document, required of the Contractor, or through the Contractor by way of a supplier, installer, manufacturer, or other lower tier contractor, the purpose of which is to further the quality or orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel, qualifications, or other verification of quality. A type of shop drawing.

SD-09, Reports: Reports of inspection and laboratory test, including analysis and interpretation of test results. Each report

shall be properly identified. Test methods used and compliance with recognized test standards shall be described.

SD-10, Test Reports: A report signed by an authorized official of a testing laboratory that a material, product, or system identical to the material, product or system to be provided has been tested in accordance with requirements specified by naming the test method and material. The test report must state the test was performed in accordance with the test requirements; state the test results; and indicate whether the material, product, or system has passed or failed the test. Testing must have been within three years of the date of award of this Contract. A type of product data.

SD-11, Factory Test Reports: A written report which includes the findings of a test required to be performed by the Contractor on an actual portion of the work or prototype prepared for this project before it is shipped to the job site. The report must be signed by an authorized official of a testing laboratory and must state the test was performed in accordance with the test requirements; state the test results; and indicate whether the material, product, or system has passed or failed the test. A type of shop drawing.

SD-12, Field Test Reports: A written report which includes the findings of a test made at the job site, in the vicinity of the job site, or on a sample taken from the job site, on a portion of the work, during or after installation. The report must be signed by an authorized official of a testing laboratory or agency and must state the test was performed in accordance with the test requirements; state the test results; and indicate whether the material, product, or system has passed or failed the test. A type of shop drawing.

SD-13, Certificates: Statements signed by responsible officials of a manufacturer of a product, system, or material attesting that the product, system, or material meet specified requirements. The statements must be dated after the award of this contract, name the project, and list the specific requirements which it is intended to address. A type of shop drawing.

SD-14, Samples: Samples, including both fabricated and unfabricated physical examples of materials, products, and units of work as complete units or as portions of units of work. A type of sample.

SD-15, Color Selection Samples: Samples of the available choice of colors, textures, and finishes of a product or material, presented over substrates identical in texture to that proposed for the work. A type of sample.

SD-16, Sample Panels: An assembly constructed at the project site in a location acceptable to the Contracting Officer and using materials and methods to be employed in the work; completely finished; maintained during construction; and removed at the conclusion of the work or when authorized by the Contracting Officer. A type of sample.

SD-17, Sample Installations: A portion of an assembly or material constructed where directed and, if approved, retained as a part of the work. A type of sample.

SD-18, Records: Documentation to ensure compliance with an administrative requirement or to establish an administrative mechanism. A type of administrative submittal.

SD-19, Operation and Maintenance Manuals: Data intended to be incorporated in an Operations and Maintenance Manual. A type of administrative submittal.

## PART 2 PRODUCTS

Not used.

## PART 3 EXECUTION

3.1 SUBMITTAL REGISTER INSTRUCTIONS: Use submittal register form for the project's Submittal Register and to track progress of submittals as they are processed.

1. The Government will supply submittal register forms, with columns (a) through (d) completed to the extent that will be required by the Government.

Column (a): Lists each specification section in which a submittal is required.

Column (b): Lists each submittal description (SD No. and type, e.g. SD-04, Drawings) required in each specification section. Follow each submittal description with the list of material or products to be addressed in each submittal description.

Column (c): Lists one principle paragraph in specification section where a material or product is specified. This listing is only to facilitate submittal reviews. Do not consider entries in

column (c) as limiting project requirements; do not consider that a blank must be filled in by Contractor or the Government.

Column (d): Indicates approving authority for each submittal. A "R" indicates approval by ROICC; a "400" indicates approval by PWC Code 400; a A/E indicates approval by the private company who designs this project; a blank indicates approval by QC Manager.

Column (e): Indicates, for submittals to be approved by Contracting Officer, specific reviewers other than QC organization. This column may or may not be filled out on the copy supplied by the Government.

2. Column (f) through (i) will be used by Contractor, QC organization and the Government on their own copies to record data established by the Contractor.

Column (f): As submittals are processed, list a consecutive number assigned by Contractor for each group of submittals, Place this same number in the appropriate block of "Submittal Transmittal Form". For a resubmission, repeat transmittal control number of the original submittal with a suffix; e.g. No. 100B" is second resubmission of material originally transmitted under No. "100."

Column (g): List dates scheduled for approving authority to receive submittals. These dates are the scheduled beginnings of submittal review period. The Contractor proposes these dates and the Contracting Officer approves them to establish the approved Submittal Register.

Column (h) and (i): Use to record Contractor's review when forwarding submittals to the QC organization.

3. Column (j) through column (o) will be used by Contractor, QC organization, and the Government on their own copies, in the following manner:

Contractor

a. Column (j): Enter date submittal is delivered to QC organization if QC Manager is approving authority or to the Government via QC organization if Contracting Officer is approving authority.

b. Columns (k) and (l): No entries are required on Contractor's copy.

c. Columns (m) and (n): Enter action and date of action by approving authority as shown on returned submittal.

d. Column (o): Enter date QC organization receives submittal from Contractor.

QC organization

a. Column (j): Enter date QC organization receives submittal from Contractor.

b. Columns (k) and (l): If approving authority is Contracting Officer, enter date QC organization forwards certified submittal to Contracting Officer.

c. Columns (m) and (n): If approving authority is Contacting Officer, enter the Government action and date of action as shown on returned submittal. If approving authority is QC Manager, enter QC action and date of action.

d. Column (o): Enter date QC organization returns submittal to Contractor, regardless of who is approving authority. If QC Manager is approving authority, it is also the date the information copy is forwarded to the Government.

Government

a. Column (j): When Contacting Officer is approving authority, enter date submittals received from QC organization.

b. Columns (k) and (l): When Contracting Officer is approving authority, enter date submittal is routed or received from specialized reviewer, such as fire protection engineer, architect-engineer, etc.

c. Columns (m) and (n): When approving authority is Contacting Officer, enter the Government action and date of action. When approving authority is QC organization, enter QC Manager action and date of action, as indicated on information copy forwarded by QC organization.

d. Column (o): When Contracting Officer is approving authority, enter date submittal is returned to Contractor via QC organization.

\*\*\* END OF SECTION \*\*\*

CONTRACTOR APPROVED SUBMITTALS (CQC)

CATALOG CUT / SHOP DRAWING TRANSMITTAL FE 4330 AND APPROVAL

SUBMITTAL NO. \_\_\_\_\_

PART I (FOR CONTRACTOR USE)

FROM:

TO:

ROICC

CONTRACT NO.

N62836-

THE FOLLOWING ITEMS ARE SUBMITTED, PER SPECIFICATION SECTION NO. \_\_\_\_\_

ITEM NO. (A)	(USE SEPARATE FORM FOR EACH SPECIFICATION SECTION) (B)	CONTRACTOR ACTION (C)	ROICC ACTION (D)

CONTRACT SPECIFICATIONS REQUIRE FACTORY  
INSPECTION      YES ☐      NO ☐

NEW SUBMITTAL ☐

RESUBMITTAL ☐

SIGNATURE

DATE

PART II (FOR ROICC USE)

FROM:

TO:

ROICC

SIGNATURE

DATE

FROM:

TO:

ROICC

ENCLOSURES RETURNED: ACKNOWLEDGEMENT OR DISAPPROVAL INDICATED ABOVE (See Column "D")

SIGNATURE

DATE

ACTION CODES: THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS SUBMITTED: (A code letter will be inserted for each item in column D section I above.)

A. APPROVED AS SUBMITTED

C. APPROVED EXCEPT AS NOTED ON DRAWINGS. REFER  
TO ATTACHED SHEET. RESUBMISSION REQUIRED.

E. DISAPPROVED SEE ATTACHED SHEET.

B. APPROVED EXCEPT AS NOTED ON  
DRAWINGS. RESUBMISSION NOT  
REQUIRED.

D. WILL BE RETURNED BY SEPARATE CORRESPONDENCE.

F. RECEIPT ACKNOWLEDGED.

NOTE: Approval of item does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

42-03-0178

01330-ATTACHMENT-1

## CATALOG CUT / SHOP DRAWING TRANSMITTAL AND APPROVAL

SUBMITTAL NO. \_\_\_\_\_

## PART I (FOR CONTRACTOR USE)

FROM:

TO:

ROICC

CONTRACT NO.

N62836-

THE FOLLOWING ITEMS ARE SUBMITTED FOR REVIEW AND APPROVAL, PER SPECIFICATION SECTION NO. \_\_\_\_\_

ITEM NO. (A)	(USE SEPARATE FORM FOR EACH SPECIFICATION SECTION) (B)	A / E Recommendation (C)	ROICC ACTION (D)

CONTRACT SPECIFICATIONS REQUIRE FACTORY  
INSPECTIONYES ☐NO ☐NEW SUBMITTAL ☐RESUBMITTAL ☐

SIGNATURE

DATE

## PART II (FOR ROICC USE)

FROM:

TO:

ROICC

REQUEST YOU REVIEW ABOVE ITEMS AND MAKE RECOMMENDATION AS REQUIRED IN A/E CONTRACT N62836-.....

SIGNATURE

DATE

## PART III (FOR DESIGNER USE)

FROM:

TO:

ROICC

ITEM HAS BEEN REVIEWED. THE FOLLOWING RECOMMENDATION IS MADE AS NOTED ABOVE. (See Column "C")

COMMENTS:

SIGNATURE

DATE

## PART IV (FOR ROICC USE)

FROM:

TO:

ROICC

ENCLOSURES RETURNED: APPROVAL OR DISAPPROVAL INDICATED ABOVE (See Column "D")

ACTION CODES: THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS SUBMITTED: (A code letter will be inserted for each item in column D section I above.)

A. APPROVED AS SUBMITTED

C. APPROVED EXCEPT AS NOTED ON DRAWINGS. REFER  
TO ATTACHED SHEET. RESUBMISSION REQUIRED.

E. DISAPPROVED SEE ATTACHED SHEET.

B. APPROVED EXCEPT AS NOTED ON  
DRAWINGS. RESUBMISSION NOT  
REQUIRED.

D. WILL BE RETURNED BY SEPARATE CORRESPONDENCE.

NOTE: Approval of item does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

SIGNATURE

DATE

42-03-0178  
01330-ATTACHMENT-2

# SUBMITTAL REGISTER (PART A)

Construction Contract No: N62836-03-C-0178

Project Title: Replace Siding, Negishi

SPEC SECTION NO	SD NO. AND TYPE OF SUBMITTAL-MATL OR PRODUCTS	SPEC PARA NO.	CLASSI F/ APPR BY CO*	GOV OR A/E REVIEW -ER	TRANS CONTROL NO.	PLANNED SUBMIT- TAL DATE
(a)	(b)	(c)	(d)	(e)	(f)	(g)

1) 01010	Certificate of insurance	1.7.1	R			
2)	Schedule of prices	1.9.1.a	OICC (via R)			
3)	As-built drawings	1.9.1.b	R			
4)	Subcontractors and personnel list	1.9.1.c	R			
5)	Vehicle list	1.9.1.d	R			
6)	Construction schedule (CPM)	1.9.1.e	R			
7) 01330	SD-18, Submittal resister	1.2.1.a	R			
8) 01450	SD-18, Quality control (QC) plan	1.2.1.a	R			
9) 01525	SD-13, Accident prevention plan (APP)	1.3.1.a	R			
10)	SD-13, Activity hazard analysis (AHA)	1.3.1.b	R			
11)	SD-13, Health and safety plan (HASP)	1.3.1.c	R			
12) 01560	Environmental protection plan	1.3.1	R			
13)	Solid waste disposal permit	1.3.2	R			
14)	Disposal permit for hazardous waste	1.3.3	R			
15) 01801	SD-08, Notification for entering with crane.	1.2.a	R			
16)	SD-13, Certification for equipment	1.2.b	R			
17)	SD-13, Certification for operators	1.2.c	R			
18)	Accident reports	1.2.d	R			
19) 02220	SD-08, Demolition plan	1.2.1.a	R			
20)	SD-13, Disposal manifest	1.2.2.a	R			
21)	SD-18, Waste identification documentation	1.2.3.a				
22) 07311	SD-02, Asphalt shingle	1.2.1.a	400			
23) 07600	SD-02, Gutter and downspout	1.2.1.a	400			
24)	SD-15, Gutter and downspout	1.2.2.a	R			
25) 09250	SD-02, Siding panel	1.2.1.a	400			
26)	SD-15, Siding panel	1.2.2.a	R			
27) 09900	SD-13, MSDS	1.2.1.a	R			
28) 13283	SD-02, Vacuum filters	1.5.1.a	R			
29)	SD-02, Respirators	1.5.1.b	R			
30)	SD-08, Qualifications of CP	1.5.2.a	R			
31)	SD-08, LBP removal plan	1.5.2.b	R			
32)	SD-08, Rental equipment notification	1.5.2.c	R			
33)	SD-08, Respiratory protection program	1.5.2.d	R			

42-03-0178

01330-ATTACHMENT-3



# SUBMITTAL REGISTER (PART A)

Construction Contract No: N62836-03-C-0178

Project Title: Replace Siding, Negishi

SPEC SECTION NO	SD NO. AND TYPE OF SUBMITTAL-MATL OR PRODUCTS	SPEC PARA NO.	CLASSI F/ APPR BY CO*	GOV OR A/E REVIEW -ER	TRANS CONTROL NO.	PLANNED SUBMIT- TAL DATE
(a)	(b)	(c)	(d)	(e)	(f)	(g)

34)	SD-08, Hazard communication program	1.5.2.e	R			
35)	SD-08, Hazardous waste management plan	1.5.2.f	R			
36)	SD-08, Hazardous waste treatment or disposal facility	1.5.2.g	R			
37)	SD-13, Vacuum filters	1.5.3.a	R			
38)	SD-18, Hazardous waste manifest	1.5.4.a	R			
39)	SD-18, Certification of medical examinations	1.5.4.b	R			
40)	SD-18, Employee training certification	1.5.4.c	R			

\* Notes:      Approved by:              R: ROICC    /      400: Code 400/Blank: CQC Manager

SUBMITTAL RESISTER (PART B)  
Contractor:

Location:

CONTRACTOR ACTION			APPROVING AUTHORITY ACTION				CONTR	
ACT CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/DATE RECD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RECD FROM OTHER REVIEWER	ACT. CODE	DATE OF ACTION	MAILED TO CONTR/ RECD FROM APPR AUTH	REMARKS
(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)

								1)
								2)
								3)
								4)
								5)
								6)
								7)
								8)
								9)
								10)
								11)
								12)
								13)
								14)
								15)
								16)
								17)
								18)
								19)
								20)
								21)
								22)
								23)
								24)
								25)
								26)
								27)
								28)
								29)
								30)
								31)
								32)
								33)
								34)
								35)
								36)
								37)
								38)
								39)
								40)

ACTION CODES: NR: Not Reviewed \ AN: Approved as Noted \ A: Approved / RR: Disapproved ; Revise and Resubmit (Others may be prescribed by the Transmittal Form)

## SECTION 01450

### QUALITY CONTROL

#### PART 1 GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 Japanese Science and Technology Agency Publication:

2000-2001            List of Testing Laboratories  
                      (Zen-koku Shiken Kenkyu Kikan Meikan)

June 2000            NAVFAC P-445 Construction Control Quality  
                      Management Program

1.2 SUBMITTALS: Submit the following in accordance with Section 01330, "Submittal Procedures."

1.2.1 SD-18, Records:

a.     Quality Control (QC) Plan: Submit a QC plan within 15 calendar days after the date of Award.

1.3 INFORMATION FOR THE CONTRACTING OFFICER: Deliver the following to the Contracting Officer:

a.     Combined Contractor Production Report(2 sheet, ATTACHMENT-1 and 2)/Contractor Quality Control Report (2 sheets, ATTACHMENT-3 and 4): Original, by 10:00 AM the next working day after each day that work is performed;

b.     Field Test Reports: 1 copy, within 2 working days after the test is performed, attached to the Contractor Quality Control Report;

c.     Monthly Summary Report of Tests: 1 copy attached to the Contractor Quality Control Report;

d.     Testing Plan and Log (1 sheet, ATTACHMENT-11): 1 copy, at the end of each month;

e.     Rework Items List (1 sheet, ATTACHMENT-10): 1 copy, by the last working day of the month

f. QC Meeting Minutes: 1 copy, within 2 working days after the meeting and;

g. QC Certifications: As required by paragraph 1.10, entitled "QC CERTIFICATIONS."

h. Monthly man-hour report

1.4 QC PROGRAM REQUIREMENTS: Establish and maintain a QC program as described in this section. The QC program consists of a QC Organization, a QC Plan, a Coordination and Mutual Understanding Meeting, three phases of control, submittal review and approval, testing, and QC certifications and documentation necessary to provide materials, equipment, workmanship, fabrication, construction and operations which comply with the requirements of this Contract. The QC program shall cover on-site and off-site work and shall be keyed to the work sequence.

1.4.1 Preliminary Work Authorized Prior to Approval: The only work that is authorized to proceed prior to the approval of the QC Plan is mobilization of storage and office trailers, temporary utilities, and surveying.

1.4.2 Approval: Approval of the QC Plan is required prior to the start of construction. The Contracting Officer reserves the right to require changes in the QC Plan and operations as necessary to ensure the specified quality of work. The Contracting Officer reserves the right to interview any member of the QC organization at any time in order to verify the submitted qualifications.

1.4.3 Notification of Changes: Notify the Contracting Officer, in writing, of any proposed change, including changes in the QC organization personnel, a minimum of seven calendar days prior to a proposed change. Proposed changes must be approved by the Contracting Officer.

#### 1.5 QC ORGANIZATION:

##### 1.5.1 QC Manager:

1.5.1.1 Duties: Provide a QC Manager at the work site to implement and manage the QC program. If the Contractor requests approval from the Contracting Officer, the QC Manager may perform the duties of project superintendent.

The QC Manager is required to be on the job site while work is in progress, and to attend the Coordination and Mutual understanding Meeting, conduct the QC meetings, perform the three phases of control,

perform submittal review, perform submittal approval, ensure testing is performed and provide QC certifications and documentation required in this Contract. The QC Manager is responsible for managing and coordinating the three phases of control and documentation performed by Testing Laboratory personnel and any other inspection and testing personnel required by this contract. The QC Manager shall provide the documentation at the meeting in the form of meeting minutes on the prescribed forms covering the topics which the attendees are scheduled to discuss at the meeting.

1.5.1.2 Qualifications: An individual with a minimum of 5 years experience as a superintendent, inspector, QC Manager, project manager, or construction manager on similar size or larger and type construction contracts which included the major trades that are part of this Contract or equivalent qualification approved by the local law.

1.5.2 Alternate QC Manager Duties and Qualifications: Designate an alternate for the QC Manager at the work site to serve in the event of the designated QC Manager's absence i.e. vacation, illness, only. The period of absence may not exceed two weeks at one time, and not more than 30 workdays during a calendar year. The qualification requirements for the Alternate QC Manager shall be the same as for the QC manager. Alternate QC manager shall not routinely fill in for QC manager to leave the job site.

1.5.3 INTERPRETER: The Contractor shall furnish the service of an interpreter on the job. This interpreter shall have strong knowledge of the English language in terms of writing, listening, speaking and reading skills. Interpreter's English skills shall also be well suited to the construction industry. If at any time the Contracting Officer feels the Contractor's interpreter is unable to perform the duties required of him/her, the Contracting Officer will ask for his/her immediate replacement. When the QC manager or the project superintendent talks with the Government's representative, the interpreter shall be present at all times.

1.5.4 Submittal Reviewers: Duties and Qualifications: Provide Submittal Reviewers, qualified in the disciplines being reviewed, to review and certify that the submittals meet the requirements of this Contract prior to certification or approval by the QC Manager.

Each submittal shall be reviewed by an individual, with 5 years of construction experience in similar size and type.

#### 1.6 QUALITY CONTROL (QC) PLAN:

1.6.1 Requirements: Provide for approval by the Contracting Officer, a QC plan submitted with pages numbered sequentially that covers, both on-site and off-site work and includes, the following:

a. A table of contents listing the major sections identified with tabs in the following order:

- I. QC ORGANIZATION
- II. NAMES AND QUALIFICATIONS
- III. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONNEL
- IV. OUTSIDE ORGANIZATIONS
- V. APPOINTMENT LETTERS
- VI. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER
- VII. TESTING LABORATORY INFORMATION VIII. TESTING PLAN AND LOG
- IX. PROCEDURES TO COMPLETE REWORK ITEMS
- X. DOCUMENTATION PROCEDURES
- XI. QUALITY CONTROL CHECKLIST
- XII. PERSONNEL MATRIX

b. A chart showing the QC organizational structure and its relationship to the production side of the organization.

c. Names and qualifications, in resume format, for each person in the QC organization.

d. Duties, responsibilities and authorities of each person in the QC organization.

e. A listing of outside organizations such as, architectural and consulting engineering firms that will be employed by the Contractor and a description of the services these firms will provide.

f. A letter signed by an officer of the firm appointing the QC Manager and stating that he/she is responsible for managing and implementing the QC program as described in this contract. Include in this letter the QC Manager's authority to direct the removal and replacement of non-conforming work.

g. Procedures for reviewing, approving and managing submittals. Provide the names of the persons in the QC organization authorized to review and certify submittals prior to approval. Provide the initial submittal or the Submittal Register as specified in Section 01330, "Submittal Procedures."

h. Testing laboratory information required by the paragraphs entitled "Testing Laboratory Requirements", as applicable.

- i. A Testing Plan and Log that includes the tests required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.
- j. Procedures to identify, record, track and complete rework items.
- k. Documentation procedures, including proposed report formats. (ATTACHMENT-5 and -6)
- l. A Quality Control Checklist that includes:
  - List of definable features of work, following the order of specification sections. Definable feature of work is a task which is separate and distinct from other tasks, and requires separate control procedures. It could be identified by different trades or disciplines, or by separate work activities. Although each section may generally be considered as a definable feature of work, there are frequently more than one definable feature under a particular section. This list will be agreed upon during the coordination and mutual understanding meeting.
  - List of construction contract numbers assigned to each preparatory, initial and follow-up phases for each definable feature of work in the construction schedule;
  - Schedule showing planned and actual dates of the preparatory, initial and follow-up phases for each definable feature of work, including testing and any other inspection required by this contract; and
  - Procedures to be followed in preparatory, initial and follow-up phases.

1.7 THREE PHASES OF CONTROL: The Three Phases of Control shall adequately cover both on-site and off-site work and shall include the following for each definable features of work.

1.7.1 Preparatory Phase: Notify the Contracting Officer at least 2 work days in advance of each preparatory phase. Conduct the preparatory phase with the superintendent, the foreman responsible for the definable feature, and the Government construction representative. The Contractor shall provide documentation at the meeting in the form of meeting minutes on the prescribed forms covering the topics to be discussed. Document the results of the preparatory phase actions in the daily Contractor Quality Control Report and in the Quality Control Checklist (ATTACHMENT-7 and -8). Perform the following prior to beginning work on each definable feature of work:

- a. Review each paragraph of the applicable specification sections;
- b. Review the Contract drawings;
- c. Verify that appropriate shop drawings and submittals for materials and equipment have been submitted and approved. Verify receipt of approved factory test results, when required;
- d. Review the testing plan and ensure that provisions have been made to provide the required QC testing;
- e. Examine the work area to ensure that the required preliminary work has been completed;
- f. Examine the required materials, equipment and sample work to ensure that they are on hand and conform to the approved shop drawings and submitted data;
- g. Review the safety plan and appropriate activity hazard analysis to ensure that applicable safety requirements are met, and that required Material Safety Data Sheets (MSDS) are submitted; and
- h. Discuss construction methods and the approach that will be used to provide quality construction through problem avoidance for each definable feature of work.

1.7.2 Initial Phase: Notify the Contracting Officer at least 5 work days in advance of each initial phase. When construction crews are ready to start work on a definable feature of work, conduct the initial phase with the superintendent, and the foreman responsible for that definable feature of work. Observe the initial segment of the definable feature of work to ensure that the work complies with Contract requirements. Document the results of the initial phase in the daily Contractor Quality Control Report and in the Quality Control Checklist (ATTACHMENT-9). Repeat the initial phase for each new crew to work on-site, or when acceptable levels of specified quality are not being met. Perform the following for each definable feature of work:

- a. Establish the quality of workmanship required;
- b. Resolve conflicts;
- c. Review the Safety Plan and the appropriate activity hazard analysis to ensure that applicable safety requirements are met; and



- d. Ensure that testing is performed by the approved laboratory.

1.7.3 Follow-Up Phase: Perform the following for on-going work daily, or more frequently as necessary until the completion of each definable feature of work and document in the daily Contractor Quality Control Report and in the Quality Control Checklist:

- a. Ensure the work is in compliance with Contract requirements;
- b. Maintain the quality of workmanship required;
- c. Ensure that testing is performed by the approved laboratory;  
and
- d. Ensure that rework items are being corrected.

1.7.4 Notification of Three Phases of Control for Off-Site Work: Notify the Contracting Officer at least two weeks prior to the start of the preparatory and initial phases.

1.8 SUBMITTAL REVIEW AND APPROVAL : Procedures for submission, review and approval of submittals are described in Section 01330, "Submittal Procedures."

1.9 TESTING: Except as stated otherwise in the specification sections, perform sampling and testing required under this Contract.

1.9.1 Testing Laboratory Requirements: Provide an independent testing laboratory which is listed on "List of Testing Laboratories (Zen-koku Shiken Kenkyu Kikan Meikan)".

1.9.2 Inspection of Testing Laboratories: Prior to approval of non-listed laboratories, the proposed testing laboratory facilities and records may be subject to inspection by the Contracting Officer. Records subject to inspection include equipment inventory, equipment calibration dates and procedures, library of test procedures, audit and inspection reports by agencies conducting laboratory evaluations and certifications, testing and management personnel qualifications, test report forms, and the internal QC procedures.

1.9.3 Capability Check: The Contracting Officer retains the right to check laboratory equipment in the proposed laboratory and the laboratory technician's testing procedures, techniques, and other items pertinent to testing, for compliance with the standards set forth in this Contract.

1.9.4 Test Results: Cite applicable Contract requirements, tests and analytical procedures used. Provide actual results and include a

statement that the item tested or analyzed conforms or fails to conform to specified requirements. If item fails to conform, notify Contracting Officer immediately. Conspicuously stamp the cover sheet for each report in large red letters "CONFORMS" or "DOES NOT CONFORM" to the specification requirements, whichever is applicable. Test results shall be signed by a testing laboratory representative authorized to sign certified test reports. Furnish the signed reports with stamp, certifications, and other documentation to the Contracting Officer via the QC Manager. Furnish a summary report of field tests at the end of each month. Attach a copy of the summary report to the last daily Contractor Quality Control Report of each month.

1.9.5 Test Reports and Monthly Summary Report of Tests: The QC Manager shall furnish the signed reports, certifications, and a summary report of field tests at the end of each month to the Contracting Officer. Attach a copy of the summary report to the last daily Contractor Quality Control Report of each month.

#### 1.10 QC CERTIFICATIONS:

1.10.1 Contractor Quality Control Report Certification: Each Contractor Quality Control Report shall contain the following statement: "On behalf of the Contractor, I certify that this report is complete and correct and equipment and material used and work performed during this reporting period is in compliance with the contract drawings and specifications to the best of my knowledge, except as noted in this report".

1.10.2 Invoice Certification: Furnish a certificate to the Contracting Officer with each payment request, signed by the QC Manager, attesting that as-built drawings are current and attesting that the work for which payment is requested, including stored material, is in compliance with contract requirements.

1.10.3 Completion Certification: Upon completion of work under this Contract, the QC Manager shall furnish a certificate to the Contracting Officer attesting that "the work has been completed, inspected, tested and is in compliance with the Contract".

1.11 DOCUMENTATION: Maintain current and complete records of on-site and off-site QC program operations and activities.

1.11.1 Contractor Production Report: Reports are required for each day that work is performed and shall be attached to the Contractor Quality Control Report prepared for the same day. Account for each calendar day throughout the life of the Contract. The reporting of work shall be identified by terminology consistent with the construction schedule. Contractor Production Reports are to be

prepared, signed and dated by the project superintendent and shall contain the following information:

a. Date of report, report number, name of contractor, Contract number, title and location of Contract and superintendent present.

b. Weather conditions in the morning and in the afternoon including maximum and minimum temperatures.

c. A list of Contractor and subcontractor personnel on the work site, their trades, employer, work location, description of work performed and hours worked.

d. A list of job safety actions taken and safety inspections conducted. Indicate that safety requirements have been met including the results on the following:

- Was a job safety meeting held? (If YES, attach a copy of the meeting minutes.)

- Were there any lost time accidents? (If YES, attach a copy of the completed OSHA report.)

- Was crane/trenching/scaffold/high voltage electrical/high work done? (If YES, attach a statement or checklist showing inspection performed.)

- Was hazardous material/waste released into the environment? (If YES, attach a description of meetings held and accidents that happened.)

e. A list of equipment/material received each day that is incorporated into the job.

f. A list of construction and plant equipment on the work site including the number of hours used, idle and down for repair.

g. Include a "remarks" section in this report which will contain pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered and a record of visitors to the work site.

1.11.2 Contractor Quality Control Report: Reports are required for each day that work is performed and for every seven consecutive calendar days of no-work and on the last day of a no-work period. Account for each calendar day throughout the life of the Contract.

The reporting of work shall be identified by terminology consistent with the construction schedule. Contractor Quality Control Reports are to be prepared, signed and dated by the QC Manager and shall contain the following information:

- a. Identify the control phase and the definable feature of work.
- b. Results of the Preparatory Phase meetings held including the location of the definable feature of work and a list of personnel present at the meeting. Indicate in the report that for this definable feature of work, the drawings and specifications have been reviewed, submittals have been approved, materials comply with approved submittals, materials are stored properly, preliminary work was done correctly, the testing plan has been reviewed, and work methods and schedule have been discussed.
- c. Results of the Initial Phase meetings held including the location of the definable feature of work and a list of personnel present at the meeting. Indicate in the report that for this definable feature of work the preliminary work was done correctly, samples have been prepared and approved, the workmanship is satisfactory, test results are acceptable, work is in compliance with the Contract, and the required testing has been performed and include a list of who performed the tests.
- d. Results of the Follow-up Phase inspections held including the location of the definable feature of work. Indicate in the report for this definable feature of work that the work complies with the Contract as approved in the Initial Phase, and that required testing has been performed and include a list of who performed the tests.
- e. Results of the three phases of control for off-site work, if applicable, including actions taken.
- f. List the rework items identified, but not corrected by close of business.
- g. List the rework items corrected from the rework items list along with the corrective action taken.
- h. Include a "remarks" section in this report which will contain pertinent information including directions received, quality control problem areas, deviations from the QC plan, construction deficiencies encountered, QC meetings held, acknowledgement that as-built drawings have been updated, corrective direction given by the QC Organization and corrective action taken by the Contractor.

i. Contractor Quality Control Report certification.

1.11.3 Testing Plan and Log: As tests are performed, the QC Manager shall record on the "Testing Plan and Log" the date the test was conducted, the date the test results were forwarded to the Contracting Officer, remarks and acknowledgment that an Contracting Officer approved testing laboratory was used. Attach a copy of the updated "Testing Plan and Log" to the last daily Contractor Quality Control Report of each month.

1.11.4 Rework Items List: The QC Manager shall maintain a list of work that does not comply with the Contract, identifying what items need to be reworked, the date the item was originally discovered, and the date the item was corrected. There is no requirement to report a rework item that is corrected the same day it is discovered. Attach a copy of the "Contractor Rework Items List" to the last daily Contractor Quality Control Report of each month. The Contractor shall be responsible for including on this list items needing rework including those identified by the Contracting Officer.

1.11.5 As-Built Drawings: The QC Manager is required to review the as-built drawings to ensure that as-built drawings are kept current on a daily basis and marked to show deviations which have been made from the Contract drawings, and to keep them at all times during work performance. The QC Manager shall initial each deviation and each revision. Upon completion of work, the QC Manager shall furnish a certificate attesting to the accuracy of the as-built drawings prior to submission to the Contracting Officer.

1.11.6 Report Forms: All reports shall be provided to the Contracting Officer in computer-generated or typewriter written. Electronic copies of these forms are available upon request from the ROICC Office. No hand-written reports will be accepted. The following forms, which are attached at the end of this section, are acceptable for providing the information required by the paragraph entitled "Documentation". While use of these specific formats are not required, any other format used shall contain the same information:

a. Combined Contractor Production Report and Contractor Quality Control Report (1 sheet), with separate continuation sheet.

b. Testing Plan and Log.

c. Deficiency Status Log (Rework Items List).

1.12 NOTIFICATION ON NON-COMPLIANCE: The Contracting Officer will notify the Contractor of any detected non-compliance with the foregoing requirements. The contractor shall take immediate

corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time for excess costs or damaged by the Contractor.

## PART 2 PRODUCTS and PART 3 EXECUTION

Not used.

\*\*\* END OF SECTION \*\*\*







<b>CONTRACTOR QUALITY CONTROL REPORT</b>				DATE	
(ATTACH ADDITIONAL SHEETS IF NECESSARY)				REPORT NO	
PHASE	CONTRACT NO	CONTRACT TITLE			
PREPARATION	WAS PREPARATORY PHASE WORK PERFORMED TODAY? YES <input type="checkbox"/> NO <input type="checkbox"/>				
	IF YES, FILL OUT AND ATTACH SUPPLEMENTAL PREPARATORY PHASE CHECK LIST				
	Schedule Activity No.	Definable Feature of work			Index #
INITIAL	WAS INITIAL PHASE WORK PERFORMED TODAY? YES <input type="checkbox"/> NO <input type="checkbox"/>				
	IF YES, FILL OUT AND ATTACH SUPPLEMENTAL PREPARATORY PHASE CHECK LIST				
	Schedule Activity No.	Definable Feature of work			Index #
FOLLOW-UP	WORK COMPLIES WITH CONTRACT AS APPROVED DURING INITIAL PHASE? YES <input type="checkbox"/> NO <input type="checkbox"/>				
	WORK COMPLIES WITH SAFETY REQUIREMENTS? YES <input type="checkbox"/> NO <input type="checkbox"/>				
	Schedule Activity No.	Definable Feature of work Section, Location and List of Personnel Present			
REWORK ITEMS IDENTIFIED TODAY (NOT CORRECTED BY CLOSE OF BUSINESS)			REWORK ITEMS CORRECTED TODAY (FROM REWORK ITEMS LIST)		
Schedule Activity No.	Description		Schedule Activity No.	Description	
REMARKS	(Also Explain Any follow-up Phase Checklist From Above That Was Answered "No", Manuf. Rep On-Site, etc)				
Schedule Activity No.	Description				
<small>On behalf of the contractor, I certify that this report is complete and correct and equipment and material Used and work performed during this reporting period is in compliance with the contract drawings and Specifications to the best of my knowledge except as noted in this report.</small>					
AUTHORIZED QC MANAGER SITE				DATE	
<b>GOVERNMENT QUALITY ASSURANCE REPORT</b>				DATE	
QUALITY ASSURANCE REPRESENTATIVES REMARKS ANOTHER EXCEPTIONS TO THE REPORT					
GOVERNMENT QUALITY ASSURANCE MANAGER				DATE	

<b>CONTRACTOR QUALITY CONTROL REPORTS</b> (CONTINUATION SHEET) (ATTACH ADDITIONAL SHEET IF NECESSARY)		DATE
		REPORT NO.
PHASE	CONTRACT NO	CONTRACT TITLE
INITIAL PHASE (CONTINUATION)	WAS INITIAL PHASE WORK PREFORMED TODAY? YES <input type="checkbox"/> NO <input type="checkbox"/>	
	IF YES, FILL OUT AND ATTACH SUPPLEMENTAL INITIAL PHASE CHECKLIST.	
	Schedule Activity No.	Definable Feature of Work
	REMARKS (Also Explain Any Checklist Item From Above That Answered "NO"). Manufacturer's Rep. On-site, etc.	
	Schedule Activity No.	Description

<b>CONTRACTOR QUALITY CONTROL REPORTS</b> (CONTINUATION SHEET) (ATTACH ADDITIONAL SHEET IF NECESSARY)		DATE
		REPORT NO.
PHASE	CONTRACT NO	CONTRACT TITLE
PREPARATORY PHASE (CONTINUATION)	WAS PREPARATORY PHASE WORK PREFORMED TODAY? YES <input type="checkbox"/> NO <input type="checkbox"/>	
	IF YES, FILL OUT AND ATTACH SUPPLEMENTAL PREPARATORY PHASE CHECKLIST.	
	Schedule Activity No.	Definable Feature of Work
	REMARKS (Also Explain Any Checklist Item From Above That Answered "NO"). Manufacturer's Rep. On-site, etc.	
	Schedule Activity No.	Description



PREPARATORY PHASE CHECKLIST		SPEC SECTION	DATE																											
(CONTINUED ON SECOND PAGE)		Enter Spec Section # Here	Enter Date (DD/MMM/YY)																											
CONTRACT NO	DEFINABLE FEATURE OF WORK	SCHEDULE ACT NO.	INDEX #																											
Enter Cnt# Here	Enter DFOV Here	Enter Sched Act ID Here	Enter Index# Here																											
PERSONNEL PRESENT	GOVERNMENT REP NOTIFIED _____ HOURS IN ADVANCE: YES <input type="checkbox"/> NO <input type="checkbox"/>																													
	<table border="1"> <thead> <tr> <th>NAME</th> <th>POSITION</th> <th>COMPANY/GOVERNMENT</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>			NAME	POSITION	COMPANY/GOVERNMENT																								
	NAME	POSITION	COMPANY/GOVERNMENT																											
SUBMITTALS	REVIEW SUBMITTALS AND/OR SUBMITTAL REGISTER. HAVE ALL SUBMITTALS BEEN APPROVED? YES <input type="checkbox"/> NO <input type="checkbox"/> IF NO, WHAT ITEMS HAVE NOT BEEN SUBMITTED? _____ _____ _____																													
	ARE ALL MATERIALS ON HAND? YES <input type="checkbox"/> NO <input type="checkbox"/> IF NO, WHAT ITEMS ARE MISSING? _____ _____																													
	CHECK APPROVED SUBMITTALS AGAINST DELIVERED MATERIAL. (THIS SHOULD BE DONE AS MATERIAL ARRIVES.) COMMENTS: _____ _____																													
MATERIAL STORAGE	ARE MATERIALS STORED PROPERLY? YES <input type="checkbox"/> NO <input type="checkbox"/> IF NO, WHAT ACTION IS TAKEN? _____ _____ _____ _____																													
SPECIFICATIONS	REVIEW EACH PARAGRAPH OF SPECIFICATIONS. _____ _____ _____																													
	DISCUSS PROCEDURE FOR ACCOMPLISHING THE WORK. _____ _____ _____																													
	CLARIFY ANY DIFFERENCES. _____ _____ _____																													
PRELIMINARY WORK & PERMITS	ENSURE PRELIMINARY WORK IS CORRECT AND PERMITS ARE ON FILE. IF NOT, WHAT ACTION IS TAKEN? _____ _____ _____ _____																													

TESTING	IDENTIFY TEST TO BE PERFORMED, FREQUENCY, AND BY WHOM.	
	WHEN REQUIRED?	
	WHERE REQUIRED?	
	REVIEW TESTING PLAN.	
SAFETY	HAS TEST FACILITIES BEEN APPROVED?	
MEETING COMMENTS	ACTIVITY HAZARD ANALYSIS APPROVED? YES <input type="checkbox"/> NO <input type="checkbox"/>	
	REVIEW APPLICABLE PORTION OF EM 385-1-1.	
OTHER ITEMS OR REMARKS	NAVY/ROICC COMMENTS DURING MEETING.	
		QC MANAGER _____ DATE _____

INITIAL PHASE CHECK LIST		SPEC SECTION	DATE
CONTRACT NO	DEFINABLE FEATURE CHECK	SCHEDULE ACT NO	INDEX#
PERSONNEL PRESENT	GOVERNMENT REP NOTIFIED ____ HOURS IN ADVANCE : YES <input type="checkbox"/> NO <input type="checkbox"/>		
	NAME	POSITION	COMPANY GOVERNMENT
PROCEDURE COMPLIANCE	IDENTIFY FULL COMPLIANCE WITH PROCEDURES IDENTIFIED AT PREPARATORY. COORDINATE PLANS SPECIFICATIONS AND SUBMITTALS		
	COMMENTS: _____		
PRELIMINARY WORK	ENSURE PRELIMINARY WORK IS COMPLETE AND CORRECT.. IF NOT, WHAT ACTION IS TAKEN?		
WORKMANSHIP	ESTABLISH LEVEL OF WORKMANSHIP		
	WHERE IS WORK LOCATED? _____		
	IS SAMPLE PANEL REQUIRED? YES <input type="checkbox"/> NO <input type="checkbox"/>		
	WILL THE INITIAL WORK BE CONSIDERED AS A SAMPLE? YES <input type="checkbox"/> NO <input type="checkbox"/> (IF YES, MAINTAIN IN PRESENT CONDITION AS LONG AS POSSIBLE AND DESCRIBE LOCATION OF SAMPLE)		
RESOLUTION	RESOLVE ANY DIFFERENCE		
	COMMENTS: _____		
CHECK SAFETY	REVIEW JOB CONDITION USING EM 385-1-1 AND JOB HAZARD ANALYSIS		
	COMMENTS: _____		
OTHER	OTHER ITEMS OR REMARKS		
<div style="display: flex; justify-content: space-between;"> <div>QC MANAGER _____</div> <div>DATE _____</div> </div>			

REV DATE: 9/98

SHEET

OF

Contractor No. and Title: \_\_\_\_\_

Contractor: \_\_\_\_\_

[illegible]



[illegible]

## SECTION 01525

### SAFETY REQUIREMENTS

#### PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

##### 1.1.1 AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI):

ANSI A10.14	(1991) Construction and Demolition Operations Requirements for Safety Belts, Harnesses, Lanyards and Lifelines for Construction and Demolition Use
ANSI Z359.1	(1992) Safety Requirements for Personal Fall Arrest Systems

##### 1.1.2 CODE OF FEDERAL REGULATIONS (CFR):

29 CFR 1910.94	Ventilation
29 CFR 1910.120	Hazardous Waste Operations and Emergency Response
29 CFR 1926.65	Hazardous Waste Operations and Emergency Response
29 CFR 1926.502(f)	Warning Line Systems

##### 1.1.3 U. S. ARMY CORPS OF ENGINEERS (USACE):

COE EM-385-1-1	(1996) Safety and Health Requirements Manual
----------------	--

##### 1.1.4 NATIONAL FIRE PROTECTION ASSOCIATION (NFPA):

NFPA 10	(1995) Portable Fire Extinguishers
NFPA 70	(1999) National Electrical Code
NFPA 241	(1996) Safeguarding Construction, Alteration, and Demolition Operations

##### 1.1.5 Japanese Laws:

Industrial Safety and Health Law, Article 81  
("Rou-dou Anzen Eisei Hou")

## 1.2 DEFINITIONS:

a. Certified Industrial Hygienist: An industrial hygienist is an individual who is certified by the American Board of Industrial Hygiene or an equivalent person who has a qualification as the labor hygiene consultant ("Rodou-eisei Konsarutanto") certified by the Industrial Safety Law, Japan.

b. Certified Safety Professional: A safety manager, safety specialist, or safety engineer that has passed the CSP exam administered by the Board of Certified Safety Professionals, or an equivalent person who has a qualification as the labor safety consultant ("Rodou-anzen Konsarutanto") certified by the Industrial Safety Law, Japan..

c. Competent Person: A competent person is one who is capable of identifying existing and predictable hazards in the surroundings or working conditions which are unsanitary, hazardous, or dangerous to employees, and who has authorization to take prompt corrective measures to eliminate them. The competent person shall have the qualification which is certified by the Japanese laws or regulations concerning a predictable hazards and dangers on the project site.

d. First Aid: First aid is any one-time treatment, and any follow-up visit for the purpose of observation, of minor scratches, cuts, burns, splinters, and so forth, which do not ordinarily require medical care, even though provided by a physician or registered professional personnel.

e. Health and Safety Plan(HASP): The HASP is the Navy equivalent Army term of SHP or SSHP used in COE EM-385-1-1. "USACE" property and equipment specified in COE EM-385-1-1 should be interpreted as Government property and equipment.

f. Lost Workdays: The number of days (consecutive or not) after, but not including, the day of injury or illness during which the employee would have worked but could not do so; that is, could not perform all or part of his normal assignment during all or any part of the workday or shift; because of the occupational injury or illness.

g. Medical Treatment: Medical treatment includes treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even through provided by a physician or registered personnel.

h. Multi-employer work site (MEWS): A multi-employer work site, as defined by OSHA, is one in which many employers occupy the same site. The Navy considers the prime contractor to be the "controlling authority" for all work site safety and health of the subcontractors.

i. Qualified Person: One who, by possession of a recognized degree, certificate, or professional standing, or extensive knowledge, training, and experience, has successfully demonstrated his or her ability to solve or resolve problems related to the subject matter, the work or the project.

j. Recordable Occupational Injuries or Illnesses: Any occupational injuries or illnesses which result in:

(1) Fatalities, regardless of the time between the injury and death, or the length of the illness; or

(2) Lost Workday Cases, other than fatalities, that result in lost workdays, or

(3) Non-Fatal Cases without lost workdays which result in transfer to another job or termination of employment, or require medical treatment (other than first aid) or involve: loss of consciousness or restriction of work or motion. This category also includes any diagnosed occupational illnesses which are reported to the employer but are not classified as fatalities or lost workday cases.

k. Safety Officer: The superintendent or other qualified or competent person who is responsible for the on-site safety required for the project. The contractor quality control person cannot be the safety officer, even though the QC has safety inspection responsibilities as part of the QC duties.

l. Serious Accidents: Any work-related incident, which results in, a fatality, in-patient hospitalization of three or more employees, or property damage in excess of ¥20,000,000.

m. Significant Accident: Any contractor accident which involves falls of 1.2 m or more, electrical accidents, confined space accidents, diving accidents, equipment accidents, crane accident or fire accidents, which, result in property damage of ¥1,000,000 or more, but less than ¥20,000,000; or when fire department or emergency medical treatment (EMT) assistance is required.

1.3 SUBMITTALS: Submit the following in accordance with Section 01330, "Submittal Procedures."

1.3.1 SD-13, Certificates:

- a. Accident Prevention Plan (APP)
- b. Activity Hazard Analysis (AHA)
- c. Health and Safety Plan (HASP)

1.4 QUALITY ASSURANCE:

1.4.1 Qualifications:

a. Qualifications of Safety Officer:

(1) Ability to manage the on-site contractor safety program through appropriate management controls.

(2) Ability to identify hazards and have the capability to expend resources necessary to abate the hazards.

(3) Must have worked on similar types of projects that are equal to or exceed the scope of the project assigned with the same responsibilities.

(4) Shall, as a minimum, have the qualification required by "Roudou Anzen Eisei-hou, 15-jou" (the Labor and Safety Health Law, Japan).

1.4.2 Meetings:

1.4.2.1 Preconstruction Conference: The safety officer shall attend the preconstruction conference.

1.4.2.2 Meeting on Work Procedures:

a. Meet with Contracting Officer to discuss work procedures and safety precautions required by the APP. Ensure the participation of the contractor's superintendent, the quality control, and the CSP or CIH.

b. Meet with Contracting Officer to discuss work procedures and safety precautions required by the HASP. Ensure the participation of the contractor's superintendent, the quality control, and the CSP or CIH.

1.4.2.3 Weekly Safety Meetings: Hold weekly at the project site. Attach minutes showing contract title, signatures of attendees and a list of topics discussed to the QC Contractor Quality Control daily report.

1.4.2.4 Work Phase Meetings: The appropriate AHA shall be reviewed and attendance documented by the Contractor at the preparatory, initial, and follow-up phases of quality control inspection.

1.4.2.5 New Employee Indoctrination: New employees will be informed of specific site hazards before they begin work. Documentation of this orientation shall be kept on file at the project site.

#### 1.4.3 Certifications:

1.4.3.1 Accident Prevention Plan (APP): Submit the APP at least 15 calendar days prior to start of work at the job site, following Appendix A of COE EM-385-1-1. Make the APP site specific. Notice To Proceed will be given after Government finds the APP acceptable.

1.4.3.2 Activity Hazard Analysis (AHA): Submit the AHA for review at least 15 calendar days prior to the start of each phase. Format subsequent AHA as amendments to the APP. In accordance with contract quality control requirements each AHA will be reviewed during an on-site preparatory inspection.

1.4.3.3 Health and Safety Plan(HASP): Submit the HASP for projects involving the handling of hazardous materials and allow 15 calendar days for review by the Safety Program Administrator, Yokosuka, OICC Far East.

1.5 ACCIDENT PREVENTION PLAN(APP): Prepare the APP in accordance with the required and advisory provisions of COE EM-385-1-1 including Appendix A, "Minimum Basic Outline for Preparation of Accident Prevention Plan," and as modified herein.

1.5.1 Hazardous Material Use: Each hazardous material shall receive approval prior to bringing onto the job site or prior to any other use in connection with this contract. Material Safety Data Sheet (MSDS) shall be prepared in each hazardous material. Allow a minimum of 10 working days for processing of the request for use of a hazardous material. Any work or storage involving hazardous chemicals or materials must be done in a manner that will not expose government employees to any unsafe or unhealthful conditions.

Adequate protective measures must be taken to prevent government employees from being exposed to any hazardous condition that could result from the work or storage. Approval by the Contracting Officer of protective measures and storage area is required prior to the start of the work.

1.6 ACTIVITY HAZARD ANALYSIS (AHA): Prepare for each phase of the work. As a minimum, define activity being performed, sequence of work, specific hazards anticipated, control measures to eliminate or reduce each hazard to acceptable levels, training requirements for all involved, and the competent person in charge of that phase of work. For work with fall hazards, including fall hazards associated with scaffold erection and removal, identify the appropriate fall arrest systems. For work with materials handling equipment, address safeguarding measures related to materials handling equipment. For work requiring excavations, include excavation safeguarding requirements. The appropriate AHA shall be reviewed and attendance documented by the Contractor at the preparatory, initial, and follow-up phases of quality control inspection.

1.7 HEALTH AND SAFETY PLAN (HASP): Prepare as required by 29 CFR 1910.120 and COE EM-385-1-1.

1.7.1 Qualified Personnel: Retain a Certified Industrial Hygienist (CIH) or a Certified Safety Professional (CSP), to prepare the HASP, conduct activity hazard analyses, and prepare detailed plan for demolition, removal, and disposal of materials. Retain the CIH or CSP for duration of contract.

1.7.2 Contents: In addition to the requirements of COE EM-385-1-1, Table 28-1, the HASP must include:

- a. Location, size, and details of control areas.
- b. Location and details of decontamination systems.
- c. Interface of trades involved in the construction.
- d. Sequencing of work.
- e. Disposal plan.
- f. Sampling protocols.
- g. Testing labs.

h. Protective equipment.

i. Pollution control.

j. Evidence of compliance with 29 CFR 1910.120 and 29 CFR 1926.65.

k. Training and certifications of CIH, CSP or other competent persons.

1.8 DRUG PREVENTION PROGRAM: Conduct a proactive drug and alcohol use prevention program for all workers, prime and subcontractor, on the site. Ensure that no employees either use illegal drugs or consume alcohol during work hours. Ensure there are no employees under the influence of drugs or alcohol during work hours. After accidents, collect blood, urine or saliva specimens and test injured employee's influence. A copy of the test shall be made available to the Contracting Officer upon request.

1.9 FALL HAZARD PROTECTION AND PREVENTION PROGRAM:

1.9.1 Scaffolds: Delineate the fall protection requirements necessary during the erection and dismantling operation of scaffolds used on the project in the Fall Protection and Prevention (FP&P) plan and activity hazard analysis for the phase of work.

1.9.2 Training: Institute a fall protection training program. As part of the Fall Hazard Protection and Prevention Program, Contractor shall provide training for each employee who might be exposed to fall hazards.

1.10 DUTIES OF THE SAFETY OFFICER:

a. Ensure construction hazards are identified and corrected.

b. Maintain applicable safety reference material on the job site.

c. Maintain a log of safety inspections performed.

d. Attend the pre-construction conference as required.

e. Identify hazardous conditions and take corrective action. Failure to do so will result in a dismissal from the site, with a work stoppage pending approval of suitable replacement personnel.



1.11 DISPLAY OF SAFETY INFORMATION: Display the following information in clear view of the on-site construction personnel:

a. Map denoting the route to the nearest emergency care facility with emergency phone numbers.

b. AHA

1.12 SITE SAFETY REFERENCE MATERIALS: Maintain safety-related references applicable to the project, including those listed in the article "References." Maintain applicable equipment manufacturers' manuals.

1.13 HIGH HAZARD WORK AND LONG DURATION: Work under this contract is potentially hazardous. Pursuant to contract clause "FAR 52.236-13, Accident Prevention, Alternate I," submit in writing additional proposals for effecting accident prevention under hazardous conditions. Meet in conference with Contracting Officer to discuss and develop mutual understanding relative to the administration of the overall safety program.

1.14 EMERGENCY MEDICAL TREATMENT: Contractors will arrange for their own emergency medical treatment. Government has no responsibility to provide emergency medical treatment. However, if emergency medical care is rendered by Navy medical services, charges may be billed to Contractor at prevailing rates established in BUMED Instruction 6320.4 series. Reimbursement shall be made by Contractor to Naval Regional Medical Center Collection Agent upon receipt of monthly statement.

1.15 REPORTS:

1.15.1 Accident Reports:

a. For recordable occupational injuries and illnesses, the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident, complete the Navy Contractor Significant Incident Report (CSIR) form and provide to the Contracting Officer within 24 hours of the accident. The Contracting Officer will provide a copy of the CSIR form.

b. For a weight handling equipment accident the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident, complete the WHE Accident Report form and provide to the Contracting Officer within 15 calendar days of the

accident. The Contracting Officer will provide a blank copy of the WHE accident report form.

1.15.2 Notification: Notify the Contracting Officer as soon as practical, but not later than four hours, of any accident meeting the definition of Recordable Occupational Injuries or Illnesses or Significant Accidents. Information shall include contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; and brief description of accident (to include type of construction equipment used, PPE used, etc.).

1.15.3 Monthly Exposure Report: Monthly exposure reporting, to the Contracting Officer is required to be attached to the monthly billing request. This report is a compilation of employee-hours worked each month for all site workers, both prime and subcontractor.

1.15.4 OSHA Citations and Violations: Provide the Contracting Officer with a copy of each OSHA citation, OSHA report and contractor response. Correct violations and citations promptly and provide written corrective actions to the Contracting Officer.

## PART 2 - PRODUCTS

2.1 SCAFFOLDING: Provide scaffolds in accordance with the Japanese Labor Safety and Sanitation Law and U.S. Department of Labor Occupational Safety and Health Administration (OSHA) Regulation, 29 CFR 1926. Provide warning signs(sign-board) on the scaffolding to prevent unauthorized persons from climbing on the scaffolding regardless of where it was located.

## PART 3 - EXECUTION

3.1 CONSTRUCTION: Comply with COE EM-385-1-1, NFPA 241, the accident prevention plan, the activity hazard analysis and other related submittals and activity fire and safety regulations.

3.1.1 Hazardous Material Exclusions: Notwithstanding any other hazardous material used in this contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation as well as materials which contain asbestos, mercury or polychlorinated

biphenyls, di-isocyanates, lead-based paint are prohibited. Exceptions to the use of any of the above excluded materials may be considered by Contracting Officer upon written request by Contractor.

3.1.2 Unforeseen Hazardous Material: The design should have identified materials such as PCB, lead paint, and friable and nonfriable asbestos. If material, not indicated, that may be hazardous to human health upon disturbance during construction operations is encountered, stop that portion of work and notify the Contracting Officer immediately. Within 15 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to "FAR 52.243-4, Changes" and "FAR 52.236-2, Differing Site Conditions."

3.2 PRE-OUTAGE COORDINATION MEETING: Contractors are required to apply for utility outages a minimum of 15 days in advance. As a minimum, the request should include the location of the outage, utilities being effected, duration of outage and any necessary sketches. Special requirements for electrical outage requests are contained elsewhere in this specification section. Once approved and prior to beginning work on the utility system requiring shut down, the Contractor shall attend a pre-outage coordination meeting with the ROICC and the Station Utilities Department to review the scope of work and the lock out/tag out procedures for worker protection. No work will be performed on energized electrical equipment unless proven impassable. Working equipment "hot" must be considered the last option.

### 3.3 PERSONNEL PROTECTION:

3.3.1 Hazardous Noise: Provide hazardous noise signs, and hearing protection, wherever equipment and work procedures produce sound-pressure levels greater than 84 dBA steady state or 140 dBA impulse, regardless of the duration of the exposure.

3.3.2 Fall Protection: Enforce use of the fall protection device designated for each specific work activity in the FP&P plan and/or AHA all times when an employee is on a surface 1.8 m or more above lower levels. Personal fall arrest systems are required when working from an articulating or extendible boom, scissor lifts, swing stages, or suspended platform. Fall protection must comply with ANSI A10.14.

3.4 SCAFFOLDING: Employees shall be provided with a safe means of access to the work area on the scaffold. Climbing of any scaffold braces or supports not specifically designed for access is prohibited. Stair towers or ladders built into scaffold systems in accordance with USACE EM 385-1-1 Appendix J are required for work platforms greater than 6 m in height. Contractor shall ensure that employees that are qualified perform scaffold erection. Do not use scaffold without the capability of supporting at least four times the maximum intended load or without appropriate fall protection as delineated in the accepted fall protection plan. Minimum platform size shall be based on the platform not being greater in height than three times the dimension of the smallest width dimension for rolling scaffold. Some Baker type scaffolding has been found not to meet these requirements. Stationary scaffolds must be attached to structural building components to safeguard against tipping forward or backward. Special care shall be given to ensure scaffold systems are not overloaded. Outrigger brackets used to extend scaffold platforms on self supported scaffold systems for the storage of material is prohibited. The first tie-in shall be at the height equal to 4 times the width of the smallest dimension of the scaffold base. Scaffold or platforms shall be provided with railing having a top rail whose upper surface is from 42-45 inches (107-114 cm) above the work surface and mid-rail located halfway between the top rail and the work surface. When necessary to prevent tools and materials from falling, toeboards of not less than 1 X 4 inch (2.5 X 10 cm) lumber shall be provided.

### 3.5 EQUIPMENT:

#### 3.5.1 Material Handling Equipment:

a. Material handling equipment such as forklifts shall not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions.

b. The use of hooks on equipment for lifting of material must be in accordance with manufacturers printed instructions.

### 3.6 ELECTRICAL:

3.6.1 Conduct of Electrical Work: Underground electrical spaces shall be certified safe for entry before entering to conduct work. Cable intended to be cut must be positively identified and de-energized prior to performing each cut. Positive cable identification must be made prior to submitting any outage request for electrical

systems. Arrangements are to be coordinated with the Contracting Officer and Station Utilities for identification. The Contracting Officer will not accept an outage request until the Contractor satisfactorily documents that the circuits have been clearly identified. Perform all high voltage cutting remotely. When racking in or live switching of circuit breakers, no additional person other than the switch operator will be allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method. When working in energized substations, only qualified electrical workers shall be permitted to enter. The entrance to all buildings, rooms, or enclosures containing exposed live parts or exposed conductors operating at over 600 volts, nominal, shall be kept locked unless such entrances are under the observation of a qualified person at all times, and where the voltage exceeds 600 volts, nominal, permanent and conspicuous warning signs shall be provided, reading as follows: DANGER-HIGH VOLTAGE-KEEP OUT. When work requires Contractor to work near energized circuits as defined by the NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety shoes, insulating gloves with leather protective sleeves, fire retarding shirts, coveralls, face shields, and safety glasses. Insulating blankets, hearing protection, and switching suits may be required, depending on the specific job and as delineated in the Contractor AHA.

### 3.7 HOUSEKEEPING:

3.7.1 Clean-up: All debris in work areas shall be cleaned up daily or more frequently as necessary. Construction debris may be temporarily located in an approved location, however garbage accumulation must be removed each day.

3.7.2 Dust Control: In addition to the dust control measures required elsewhere in the contract documents dry cutting of brick or masonry shall be prohibited. Wet cutting must address control of water run off.

3.8 ACCIDENT SCENE PRESERVATION: For serious accidents, and accidents involving weight handling equipment, ensure the accident site is secured and evidence is protected remaining undisturbed until released by the Contracting Officer.

### 3.9 FIELD QUALITY CONTROL:

3.9.1 Inspections: Include safety inspection as a part of the daily Quality Control inspections required in Section 01450, "Quality Control".

3.9.2 VEHICLES: Amount of vehicles and parking area for on-site work shall be under the direction of the Contracting Officer. No personal vehicles are allowed except for transportation of materials, equipment, employees, and others related for this project.

3.9.3 SMOKING AREA: The Contractor's smoking area shall be under the direction of the Contracting Officer.

\*\*\* END OF SECTION \*\*\*

## SECTION 01560

### ENVIRONMENTAL PROTECTION

#### PART 1 - GENERAL

1.1 REFERENCES: The publications listed below forms a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

##### 1.1.1 Japanese Law (JL):

No.132	The Environmental Pollution Prevention Act.
No. 97	The Air Pollution Control Act (Clean Air Act)
No.138	The Water Pollution Prevention Act.
No.136	The Sea Pollution Prevention Act.
No.139	The Agricultural Soil Pollution Prevention Act.
No. 98	The Noise Control Act.
No. 64	The Oscillation (Vibration) Control Act.
No.137	The Waste Disposal and Cleaning Act.
No. 85	The National Environment Conservation Act.

##### 1.1.2 Kanagawa Prefectural Office's Publication:

"Kanagawa-ken Kohgai Bohshi Jyorei Kitei Shu (Heisei 4 nendo)"  
(Handbook for Pollution Control Laws and Official Regulations)

##### 1.1.3 Notification of the Environment Agency, Japan:

No. 13                      Detection Method for the Presence of Toxicity

##### 1.1.4 U.S. Department of Labor, Occupational Safety and Health Administration (OSHA) Regulation:

9 CFR 1910.94      Occupational Health and Environmental Control

1.1.5 DOD Japanese Environmental Governing Standards (JEGS), accomplished by US Forces Japan, American Embassy, and Japanese Government Agencies, June 2002.

##### 1.2 DEFINITIONS:

1.2.1 Sediment: Soil and other debris that have eroded and transported by runoff water or wind.

1.2.2 Solid Waste: Rubbish, debris, garbage, and other discarded solid materials, except hazardous waste as defined in paragraph entitled, "Hazardous Waste," resulting from industrial, commercial, and agricultural operations, and from community activities.

1.2.3 Rubbish: Combustible and noncombustible wastes such as paper, boxes, glass, crockery, metal, lumber, cans, and bones.

1.2.4 Debris: Combustible and noncombustible wastes such as ashes and waste materials resulting from construction or maintenance and repair work, leaves, and tree trimmings.

1.2.5 Chemical Waste: This includes salts, acids, alkalies, herbicides, pesticides, and organic chemicals.

1.2.6 Sanitary Wastes:

1.2.6.1 Sewage: Waste characterized as domestic sanitary sewage.

1.2.6.2 Garbage: Refuse and scraps resulting from preparation, cooking, dispensing, and consumption of food.

1.2.7 Hazardous Waste: Hazardous substances as defined in JEGS 6-2.10.

1.2.8 Oily Waste: Petroleum products and bituminous materials.

1.3 SUBMITTALS: Submit the following in accordance with Section 01330, "Submittal Procedures."

1.3.1 Environmental Protection Plan: Submit four copies of the proposed environmental protection plan. Environmental protection plan includes all permits and disposal documentation regarding work performed under this contract, and protection plan for hazardous material spill response.

1.3.2 Solid Waste Disposal Permit: Submit one copy of Japanese local permit and license showing such agencies' approval of the disposal plan.

1.3.3 Disposal Permit for Hazardous Waste: Submit a copy of the applicable Japanese local permits and licenses for transportation, treatment, storage and disposal of hazardous waste by permitted facilities.

1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS: Provide and maintain during the life of the contract, environmental protection as defined. Plan for and provide environmental protective measures to control pollution that develops during normal construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Comply with the regulations, listed under paragraph "References", pertaining to the environment. In the event of conflict among any of the cited regulations the most stringent shall govern.



1.4.1 Environmental Protection Plan: Five days after the award of contract, the Contractor shall meet with the Contracting Officer to discuss the proposed environmental protection plan and to develop mutual understanding relative to the details of environmental protection, including measures for protecting natural resources, required reports, and other measures to be taken.

1.4.1.1 Fourteen days after the meeting, the Contractor shall submit to the Contracting Officer the proposed environment plan for further discussion, review, and approval.

1.4.1.2 Commencement of the Work: As directed by the Contracting Officer, following approval.

1.4.2 Preconstruction Survey: Perform a preconstruction survey of the project site with the Contracting Officer, and take photographs showing existing environmental conditions in and adjacent to the site.

1.5 PROHIBITED MATERIALS: Prohibit the following materials to be used.

- a. Materials containing asbestos.
- b. Drinking water components or fixtures that contains greater than 8% lead (pipes, fittings, and fixtures) or 0.2% lead (flux and solders).
- c. Paint that contains more than 0.06% lead by weight in the total non-volatile content of liquid paint.
- d. Materials containing PCBs (2 ppm and above).

## PART 2 - EXECUTION

2.1 PROTECTION OF NATURAL RESOURCES: Preserve the natural resources within the project boundaries and outside the limits of permanent work. Restore to an equivalent or improved condition upon completion of the work. Confine construction activities to within the limits of the indicated or specified.

2.1.1 Land Resources: Except in areas to be cleared, do not remove, cut, deface, injure, or destroy trees or shrubs without the Contracting Officer's permission. Do not fasten or attach ropes, cables, or guys to existing nearby trees for anchorages, unless authorized by the Contracting Officer. Where such use of attach ropes, cables, or guys is authorized, the Contractor shall be responsible for any resultant damage.

2.1.1.1 Protection: Protect existing trees which are to remain and which may be injured, bruised, defaced, or otherwise damaged by construction operation. Remove displaced rocks from uncleared areas. By approved excavation, remove trees with 30 percent or more of their

root systems destroyed.

2.1.1.2 Replacement: Remove plants, trees, and other landscape features scarred or damaged by equipment operations, and replace with equivalent, undamaged trees and landscape features. Obtain the Contracting Officer's approval before replacement.

2.1.1.3 Temporary Construction: Remove traces of temporary construction facilities such as haul roads, work areas, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other signs of construction. Grade temporary roads, parking areas, and similar temporarily used areas to conform with surrounding contours.

2.1.2 Storm Water: The Contractor shall plan for and provide controls to prevent storm water run off containing sediments and other debris from leaving the site. The Contractor will collect and dispose of all sediments and debris accumulated.

2.2 DUST CONTROL: Keep dust down at all times, including during nonworking periods. Sprinkle or treat, with dust suppressants, the soil at the site, haul roads, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead, use vacuuming, wet sweeping, or wet power brooming. Only wet cutting will be permitted for cutting concrete blocks, concrete, and bituminous concrete. Do not unnecessarily shake bags of cement, concrete mortar, or plaster.

2.2.1 Hazardous Waste(HW): The Contractor shall not dispose of any materials classified as hazardous waste, or asbestos. The Contractor shall establish a HW Accumulation Point (JEGS 6-3.2) where all suspected HW will be managed. Public Work Team Environmental Division(PWTED) will sample the waste to determine if it is HW. If the determination is HW, it will be packaged in accordance with JEGS requirements and turned over to the Government for disposal. The Contractor shall transport and deliver HW to a site on Yokosuka Naval Base as designated by the Contracting Officer's representative. Contact PWTED at 243-2732 to request sampling/testing.

2.3 HAZARDOUS WASTE DISPOSAL: The Government will not permit the to dispose of HW, as specified in paragraph 2.2.1 "Hazardous Waste."

\*\*\* END OF SECTION \*\*\*

## SECTION 01801

### SAFETY REQUIREMENTS FOR CRANE OPERATION

#### PART 1 - GENERAL

1.1 REFERENCES: The publications listed below forms a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 U.S. Army Corps of Engineers:

EM 385-1-1            Safety and Health Requirements Manual

1.1.2 U.S. Navy Publication (P-Pub):

P-307                Management of Weight Handling Equipment

1.2 SUBMITTALS: Submit the following items to the Contracting Officer;

- a. SD-08, Notification for entering with crane.
- b. SD-13, Certification for equipment
- c. SD-13, Certification for operators
- d. Accident reports.

1.3 RULES AND REQUIREMENTS: Any crane entering any Naval activity in Japan shall conform to EM-385-1-1, P-307, Prefectural Labor Standards Office rules, and requirements concerning the safe operating conditions and safe operations of that crane.

1.4 NOTIFICATION: The Contractor with cranes entering the activity shall notify the ROICC in writing at least 48 hours before entry of crane.

1.5 CERTIFICATIONS FOR EQUIPEMNT: The Contractor shall certify that the crane and rigging gear conform to the GOJ Safety Standards per the certification statements, paragraph 1, of the blank form ("Certificate of Compliance") attached as ATTACHMENT-1 at the end of this section. The Contractor shall also certify, using the same form, certification statement paragraph 3, that all crane operators working on the Naval activity have been trained not to ignore safety devices (such as anti-two blocking devices) during lift operations.

1.6 CERTIFICATIONS FOR OPERATORS: The Contractor shall certify the crane operators are qualified and trained for the operation of the crane using the blank form ("Certificate of Compliance") attached as ATTACHMENT-1 at the end of this section. Post the completed copy of ATTACHMENT-1 in a visible portion of the crane operator's cab. Complete and post the completed copy of ATTACHMENT-1 in a visible portion of the crane operator's cab. The Contracting Officers and representatives of the host activities will perform on-site-spot checks to assure that crane safety is observed and any unsafe conditions or actions will cause the stoppage of the crane work. On-site-post checks will be documented using ("Contractor Crane Operation Checklist") attached as ATTACHMENT-2 at the end of this section.

1.7 DOCUMENTATION: The prime Contractor shall have documentation for the testing and operating exam in order to make it valid. The training and operating exam can have been done by Japanese Labor Standards Bureau or designated training agency. The key is to be able to show us the training outline, qualifications of the trainer, the test questions given and what the operational exam consisted of. After completion of the training, etc, the operator shall be given a license or certificate of completion. Retaining shall be done after any accident has occurred and refresher training at least every 3 years.

#### 1.8 ACCIDENT:

1.8.1 Notifying: The Contractor shall notify the Contracting Officer of a crane accident as soon as practical after the accident has occurred (no longer than two hours). The accident scene shall be secured and evidence protected until released by the Contracting Officer. Crane operations shall not be continued until a cause is determined and corrective actions are in place to the satisfaction of the Contracting Officer.

1.8.2 Reports: Within 30 calendar days, the Contractor shall provide a weight handling accident report using form ("WEIGHT HANDLING EQUIPMENT ACCIDENT REPORT" with instructions, reference to attachments 3 and 4, attached at the end of this section) consisting of a summary of circumstances, an explanation of cause, photographs, and corrective actions taken.

PART 2 and PART 3

Not used.

\*\*\* END OF SECTION \*\*\*

42-03-0178  
01801-3

# CERTIFICATE OF COMPLIANCE

This certificate shall be signed by an official of the company that provides cranes for any application under this contract. Post a completed certificate on each crane brought onto Navy property.

PRIME CONTRACTOR /PHONE:

CONTRACT NUMBER:

CRANE SUPPLIER/PHONE:  
(if different from prime contractor)

CRANE NUMBER:  
(i.e., ID number)

CRANE MANUFACTURER/TYPE/CAPACITY:

CRANE OPERATOR'S NAME(S):

I certify that:

1. The above noted crane conforms to applicable OSHA regulations (host country regulations for naval activities in foreign countries). The following regulations apply: EM 385-1-1, SECTION 16.C, Appendix G, H and I, Where more stringent crane standards are set forth, the more stringent standards shall apply.

2. That the operator(s) noted above have been trained, tested (orally or written and practical operating examination) and are qualified for the operation of the above noted crane. I have included that the operator must have been tested, either orally or written, and that a practical operating exam has been administered. These requirements need to be done for each different type, manufacturer and size of crane.

3. That the operators noted above have been trained not to bypass safety devices during lifting operations.

COMPANY OFFICIAL SIGNATURE:

DATE:

**POST ON CRANE**  
(IN CAB OR VEHICLE)

# CONTRACTOR CRANE OPERATION CHECKLIST

		YES	NO
1.	Does the operator know the weight of the load to be lifted?		
2.	Is the load to be lifted within the crane manufacturer's rated capacity in its present configuration?		
3.	Is the crane level and on firm ground?		
4.	Are outriggers required?		
5.	If so, are outriggers fully extended and down, and the crane load off the wheels?		
6.	If blocking is required, is the entire surface of the outrigger pad supported and is the blocking material of sufficient strength to safely support the loaded outrigger pad?		
7.	If outriggers are not used, is the crane rated for on-rubber lifts by the manufacturer's load chart?		
8.	Is the swing radius of the crane counterweight clear of people and obstructions and accessible areas within the swing area barricaded to prevent injury or damage?		
9.	Has the hook been centered over the load in such a manner to minimize swing?		
10.	Is the load well secured and balanced in the sling or lifting device before it is lifted more than a few inches?		
11.	Is the lift and swing path clear of obstructions?		
12.	If rotation of the load being lifted is hazardous, is a tag or restraint line being used?		
13.	Are personnel prevented from standing or passing under a suspended load?		
14.	Is the crane operator's attention diverted?		
15.	Are proper signals being used at all times?		
16.	Do the operations ensure that side loading is prohibited?		
17.	Are personnel prevented from riding on a load?		
18.	Are start and stop motions in a smooth fluid motion (no sudden acceleration or deceleration)?		
19.	If the load is to be suspended and left unattended, have prior planning and written procedures been completed?		
20.	If operating near electric power lines, are the rules and guidelines understood and adhered to?		
21.	Is the lift a critical lift?		
22.	If so, are all regulations understood and check-off sheets initialed and signed off?		
23.	Is the operator qualified to operate crane? Viewed documentation?		
<b>Contractor:</b>		<b>Subcontractor:</b>	
<b>Location:</b>		<b>Date:</b>	
<b>Notes:</b>			

<b>WEIGHT HANDLING EQUIPMENT ACCIDENT REPORT</b>					Report Date:
From:			To: Navy Crane Center, NORTHNAVFACENGCOM 10 Industrial Hwy; MS #82 Lester, PA 19113-2090 FAX (610) 595-0748		
UIC:					
Activity:				Report No:	
Crane No:		Cat:		Accident Date	
Time: hrs					
SPS:		GPS:		Crane Type:	
Crane Manufacturer:					
Location:				Weather:	
Crane Capacity:		Hook Capacity:		Weight of Load on Hook:	
NAVSAFECEN Reportable		YES		NO	
				Damage Cost Estimate	
				Only if >\$10,000	
<b>Accident Type:</b> <div style="display: flex; flex-wrap: wrap;"> <div style="width: 50%;"><input type="checkbox"/> Personal Injury</div> <div style="width: 50%;"><input type="checkbox"/> Overload</div> <div style="width: 50%;"><input type="checkbox"/> Derail</div> <div style="width: 50%;"><input type="checkbox"/> Damaged Rigging Gear</div> <div style="width: 50%;"><input type="checkbox"/> Load Collision</div> <div style="width: 50%;"><input type="checkbox"/> Two Blocked</div> <div style="width: 50%;"><input type="checkbox"/> Dropped Load</div> <div style="width: 50%;"><input type="checkbox"/> Damaged Crane</div> <div style="width: 50%;"><input type="checkbox"/> Crane Collision</div> <div style="width: 50%;"><input type="checkbox"/> Damaged Load</div> <div style="width: 50%;"><input type="checkbox"/> Other _____ Specify</div> </div>					
<b>Cause of Accident:</b> <div style="display: flex; flex-wrap: wrap;"> <div style="width: 50%;"><input type="checkbox"/> Improper Operation</div> <div style="width: 50%;"><input type="checkbox"/> Equipment Failure</div> <div style="width: 50%;"><input type="checkbox"/> Inadequate Visibility</div> <div style="width: 50%;"><input type="checkbox"/> Improper Rigging</div> <div style="width: 50%;"><input type="checkbox"/> Switch Alignment</div> <div style="width: 50%;"><input type="checkbox"/> Inadequate Communication</div> <div style="width: 50%;"><input type="checkbox"/> Track Condition</div> <div style="width: 50%;"><input type="checkbox"/> Procedural Failure</div> <div style="width: 50%;"><input type="checkbox"/> Other _____ Specify</div> </div>					
<b>Chargeable To:</b> <div style="display: flex; flex-wrap: wrap;"> <div style="width: 50%;"><input type="checkbox"/> Track Walker</div> <div style="width: 50%;"><input type="checkbox"/> Rigger</div> <div style="width: 50%;"><input type="checkbox"/> Operator</div> <div style="width: 50%;"><input type="checkbox"/> Maintenance</div> <div style="width: 50%;"><input type="checkbox"/> Management/Supervision</div> <div style="width: 50%;"><input type="checkbox"/> Other _____ Specify</div> </div>					
<b>Crane Function</b> <input type="checkbox"/> Travel <input type="checkbox"/> Hoist <input type="checkbox"/> Rotate <input type="checkbox"/> Luffing <input type="checkbox"/> Lower <input type="checkbox"/> Telescoping					
Is this accident indicative of a recurring problem? <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, list Accident Report Nos.: _____					
<b>ATTACH COMPLETE AND CONCISE SITUATION DESCRIPTION AND CORRECTIVE /PREVENTIVE ACTIONS TAKEN AS ENCLOSURE (1).</b> Includes probable cause and contributing factors. Assess damages And define responsibility. For equipment malfunction or failure include specific description of the Component and the resulting effect or problem caused by the malfunction or failure. List Corrective/ Preventive Actions assigned and responsible codes					
Preparer's Signature			Code		Date
<b>CONCURRENCES (Include Signature, Code, and date)</b>					
<b>CERTIFYING OFFICIAL</b>					



## WEIGHT HANDLING EQUIPMENT ACCIDENT REPORT INSTRUCTIONS

Block 1 - Report Date: The date the accident report is completed.

Block 2 – From: The naval activity that owns the crane and UIC number.

Block 3 – Activity: The naval activity where the accident took place.

Block 4 – Report No.: The activity assigned accident number (e.g., 95-001).

Block 5 – Crane No.: The activity assigned crane number (e.g., PC-5).

Block 6 – Category: Identify category of crane (i.e., 1,2,or 3).

Block 7 – Accident Date: The date the accident occurred (month/day/year).

Block 8 – Time: The time (24 hour clock) the accident occurred (e.g., 1300).

Block 9 – Category of Service: Special purpose service (SPS) or general purpose service (GPS).

Block 10 – Crane Type: The type of crane involved in the accident (e.g., mobile, bridge).

Block 11 – Crane Manufacturer: The manufacturer of the crane (e.g., Dravo, Grove, P&H).

Block 12 – Location: The detailed location where the accident took place (e.g., building 213, dry dock 5).

Block 13 – Weather: The weather conditions at time of accident (e.g., wind, rain, cold).

Block 14 – Crane Capacity: The certified capacity of the crane (e.g., 60 tons).

Block 15 – Hook Capacity: The capacity of the hook involved in the accident at the maximum radius of the operation.

Block 16 – Weight of Load on Hook: If applicable, the weight of the load on the hook.

Block 17 – NAVSAFECEN Reportable: Check yes or no. See OPNAVINST 5100.23 for more information.

Block 18 – Dmg Cost Estimate: Estimate total cost of damage resulting from the accident if greater than (>)\$10,000.

Block 19 – Accident Type: Check all that apply.

Block 20 – Cause of Accident: Check all that apply.

Block 21 – Chargeable to: Check all that apply.

Block 22 – Crane Function: Check the function(s) in operation at time of accident. Check all that apply.

Block 23 – Is this a recurring problem?: Check yes or no. Identify any other similar accidents.

Block 24 – Situation Description/Corrective Actions: Self-explanatory.

Block 25 – Concurrence: Signatures of activity personnel verifying the accident report.

DIVISION 2  
SITE WORK  
SECTION 02220  
SITE DEMOLITION

PART 1 - GENERAL

1.1 REFERENCES: The following publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 Department of Defense Japan Environmental Governing Standard issued by Headquarters, U.S. Forces Japan, (JEGS), October 2001, Version 1.1(Revised: June 2002).

1.2 SUBMITTALS: Submit the following in accordance with Section 01330, "Submittal Procedures."

1.2.1 SD-08, Statements:

a. Demolition Plan: Submit proposed demolition and removal procedures to the Contracting Officer for approval before work is started.

1.2.2 SD-13, Certificates:

a. Disposal manifest

1.2.3 SD-18, Records: Submit waste identification documentation in accordance with JEGS and GOJ.

a. Waste identification documentation

1.3 GENERAL REQUIREMENTS: Do not begin demolition until authorization is received from the Contracting Officer. Remove rubbish and debris from the project site; do not allow accumulations around the work area. Store materials that cannot be removed daily in areas specified by the Contracting Officer.

1.4 REGULATORY AND SAFETY REQUIREMENTS: Comply with federal, GOJ, prefectural, local, and Japan Environmental Governing Standards (JEGS) regarding hauling and disposal regulations.

1.5 DUST AND DEBRIS CONTROL: Prevent the spread of dust and debris to occupied portions of the work site and avoid the creation

of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution. Vacuum and dust the work area daily.

#### 1.6 PROTECTION:

1.6.1 Traffic Control Signs: Where pedestrian and driver safety is endangered in the area of removal work, use traffic barricades with flashing lights. Notify the Contracting Officer prior to beginning such work.

1.6.2 Existing Work: Protect existing work which is to remain in place, be reused, or remain the property of the Government. Repair items which are to remain and which are damaged during performance of the work to their original condition, or replace with new. Do not overload structural elements. Provide new supports and reinforcement for existing construction weakened by demolition or removal work. Repairs, reinforcement, or structural replacement shall have Contracting Officer approval.

1.6.3 Weather Protection: For portions of the building to remain, protect building interior and materials and equipment from the weather at all times.

1.6.4 Facilities: Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities.

1.7 BURNING: Burning will not be permitted.

1.8 RELOCATIONS: Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the trades involved. Repair items to be relocated which are damaged or replace damaged items with new undamaged items as approved by the Contracting Officer.

## PART 2 - PRODUCTS

Not used.

## PART 3 - EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED: As indicated on drawing.

3.1.1 Removal and Disposal of Existing Lead-based Paint(LBP): Existing paint material on wood and galvanized steel surface contains LBP. Handling of existing LBP shall be as specified in Section 13283, "Removal and Disposal of Lead-containing Paint".

### 3.2 DISPOSITION OF MATERIAL:

3.2.1 Title to Materials: Except where specified, all materials and equipment removed shall become the property of the Contractor and shall be removed from Government property. Title to materials resulting from demolition, and materials and equipment to be removed, is vested in the Contractor upon approval by the Contracting Officer of the Contractor's demolition and removal procedures, and authorization by the Contracting Officer to begin demolition. The Government will not be responsible for the condition or loss of, or damage to, such property after notice to proceed. Materials and equipment shall not be viewed by prospective purchasers or sold on the site.

### 3.3 CLEANUP:

3.3.1 Debris and Rubbish: Remove and transport debris and rubbish in a manner that will prevent spillage on pavements, streets or adjacent areas.

\*\*\* END OF SECTION \*\*\*

DIVISION 6  
WOOD AND PLASTICS  
SECTION 06200  
ROUGH AND FINISH CARPENTRY

PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the designation only.

1.1.1 Japanese Architectural Standards Specification:

JASS 11-68          Carpentry

1.1.2 Japanese Agricultural Standards (JAS) Association  
Publications:

SL-86          Sawn Lumber  
OP-86          Ordinary Plywood

1.2 DELIVERY AND STORAGE: In accordance with JASS 11.

1.3 GRADING AND MARKING:

1.3.1 Lumber: Identify each piece or each bundle of lumber, millwork, and trim by the grade mark of a recognized association or independent inspection agency that is certified by the Minister of Japanese Agriculture, Forestry, and Fishery to grade the species.

1.3.2 Plywood: Mark each sheet with the mark of a recognized association or independent inspection agency that maintains continuing control over the quality of the plywood.

1.4 SIZES AND SURFACING: Lumber shall be surfaced four sides. Size references, unless otherwise specified, are nominal sizes, and actual sizes shall be within manufacturing tolerances allowed by the standard under which the product is produced.

1.5 MOISTURE CONTENT OF WOOD PRODUCT: Air-dry or kiln-dry lumber.

PART 2 - PRODUCTS:

2.1 MATERIALS: Materials not otherwise specified herein shall conform to JASS 11.

2.1.1 Lumber and Wood: JAS "Sawn Lumber," Class No.1, as indicated on drawing.

2.1.1.1 Window Trim: Japanese Cryptomeria(Sugi).

2.1.2 Plywood: JAS "Ordinary Plywood", Type 1-Rui, as indicated on drawing.

PART 3 - EXECUTION

3.1 WORKMANSHIP: In accordance with JASS 11 and the each manufacturer's instruction.

\*\*\* END OF SECTION \*\*\*

DIVISION 7

THERMAL AND MOISTURE PROTECTION

SECTION 07311

ASPHALT SHINGLES

PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 Japanese Industrial Standards (JIS):

A 6005-91	Asphalt Roofing Felts
A 5423-95	Decorated Cement Shingles for Dwelling Roofs

1.1.2 Japanese Architectural Standards Specification:

JASS 12-90	Roof Coverings
------------	----------------

1.2 SUBMITTALS: Submit the following items as specified in Section 01330, "Submittal Procedures".

1.2.1 SD-02, Manufacturer's Catalog Data:

a. Asphalt shingle

1.3 DELIVERY, STORAGE, AND HANDLING: In accordance with JASS 12.

1.4 WARRANTY:

1.4.1 Manufacture's Warranty: Furnish the asphalt shingle manufacture's standard 10-year warranty for the asphalt shingle. The warranty shall run directory to the Government.

1.4.2 Contractor's Warranty: The Contractor shall warrant for 5-year that the asphalt shingle roofing system, as installed, is free from defects in workmanship. When repairs due to defective workmanship are required during the Contractor's warranty period, the Contractor shall make such repairs within 72 hours of notification. When repairs are not performed within the specified time, emergency repairs performed by others will no void the warranty.

## PART 2 - PRODUCTS

### 2.1 MATERIALS:

2.1.1 Asphalt Shingle: JIS A 5423, as indicated on drawing.

2.1.2 Asphalt Roofing: JIS A 6005, Type 940.

## PART 3 - EXECUTION

3.1 INSTALLATION: In accordance with JASS 12 and the each manufacturer's approved installation instructions.

\*\*\* END OF SECTION \*\*\*



## SECTION 07600

### GUTTER AND DOWNSPOUT

#### PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 Japanese Industrial Standards (JIS):

K 6741-99	Unplasticized Polyvinyl Chloride (PVC) Pipes
G 3302-94	Hot-dip Zinc-coated Steel Sheets and Coils

1.1.2 Japanese Architectural Standards Specification:

JASS 12-90	Roof Coverings
------------	----------------

1.2 SUBMITTALS: Submit the following items as specified in Section 01330, "Submittal Procedures".

1.2.1 SD-02, Manufacturer's Catalog Data:

a. Gutter and Downspout

1.2.2 SD-15, Color Selection Sample:

a. Gutter and Downspout

1.3 DELIVERY, STORAGE, AND HANDLING: In accordance with JASS 12.

#### PART 2 - PRODUCTS

2.1 MATERIALS:

2.1.1 Gutter: Colored type polyvinyl chloride (PVC) gutter, as indicated on drawing.

2.1.2 Downspout: JIS A 6741, Type VU, colored type, as indicated on drawing.

2.1.3 Hanger and Leader Strap: Galvanized steel (GS), JIS G 3302.

PART 3 - EXECUTION

3.1 WORK PROCEDURE: In accordance with JASS 12 and the each manufacturer's instruction.

\*\*\* END OF SECTION \*\*\*

## SECTION 07920

### SEALANT

#### PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 Japanese Architectural Standards Specification:

JASS 8-00            Waterproofing and Sealing

1.1.2 Japanese Industrial Standard (JIS):

A 5758-97            Sealants for Sealing and Glazing in Buildings

1.2 ENVIRONMENTAL CONDITIONS: In accordance with JASS 8.

1.3 DELIVERY AND STORAGE: In accordance with JASS 8.

#### PART 2 - PRODUCTS

2.1 MATERIALS:

2.1.1 Sealant: JIS A 5758, Type PU

2.1.2 Primer: Provide a nonstaining, quick-drying type of consistency in accordance with the sealant manufacturer for the particular application.

2.1.3 Bond Breaker: Provide the type and consistency in accordance with the sealant manufacturer for the particular application.

2.1.4 Backstops: Provide glass fiber roving or neoprene, butyl, polyurethane, or polyethylene foams free from oil or other staining elements in accordance with the sealant manufacturer. Backstop material shall be compatible with sealant.

2.1.5 Cleaning Solvents: Provide type(s) in accordance with the sealant manufacturer.

PART 3 - EXECUTION

3.1 WORK PROCEDURE: In accordance with JASS 8 and the each manufacturer's instruction.

\*\*\* END OF SECTION \*\*\*

DIVISION 9

FINISHES

SECTION 09250

CEMENT BOARD SIDING

PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 Japanese Industrial Standards (JIS):

A 5422-02	Fiber Reinforced Cement Siding
A 6005-91	Asphalt Roofing Felts
G 4305-99	Cold Rolled Stainless Steel Plates, Sheets and Strip
G 3302-98	Hot-dip Zinc-coated Steel Sheets and Coils

1.2 SUBMITTALS: Submit the following items as specified in Section 01330, "Submittal Procedures".

1.2.1 SD-02, Manufacturer's Catalog Data:

a. Siding panel

1.2.2 SD-15, Color Selection Sample:

a. Siding panel

1.3 DELIVERY, HANDLING, AND STORAGE: In accordance with the siding panel manufacturer.

PART 2 - PRODUCTS

2.1 MATERIALS:

2.1.1 Siding Panel: Pre-coated, decorative wooden pattern fiber reinforced cement board siding, JIS A 5422, Type-D, with colored stainless steel (SST, JIS G 4305, SUS 304) screw nail, metal joiner,

sealant, and relate items, as indicated on drawing. Siding to be installed over the canopy roof and lean-to roof shall be detachable for the future siding maintenance.

2.1.2 Asphalt Felt: JIS A 6005, Type 430.

2.1.3 Flashing: Galvanized steel(JIS G 3302).

### PART 3 - EXECUTION

3.1 APPLICATION: In accordance with the each manufacturer's instruction.

\*\*\* END OF SECTION \*\*\*

## SECTION 09900

### PAINTS AND COATINGS

#### PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 Steel Structures Painting Council (SSPC) Specifications:

SSPC-SP 1-82      Solvent Cleaning

1.1.2 Japan Paint Manufacturer's Association (JPMA) Publication:

2001 A      Paint Color Samples

1.1.3 Japanese Architectural Standard Specification:

JASS 18-98      Paint Work

1.1.4 Japanese Industrial Standards (JIS):

K 5516-03	Ready Mixed Paint (Synthetic Resin Type)
K 5582-03	Vinyl Chloride Resin Enamel
K 5583-03	Vinyl Chloride Resin Primer
K 5629-02	Calcium Plumbate Anticorrosive Paint

1.1.5 Code of Federal Regulations (CFR):

29 CFR 1910.1000      Air Contaminants

1.2 SUBMITTALS: Submit the following items as specified in Section 01330, "Submittal Procedures".

1.2.1 SD-13, Certificates:

a. Manufacturer's Material Safety Data Sheets(MSDS): Submit for coatings, solvents, and other potentially hazardous materials, as defined in the Japanese Labor, Safety and Sanitation Law; and Japanese Regulation of Organic Solvent Toxication Prevention.

1.3 QUALITY ASSURANCE:

1.3.1 Qualification of Airless Spray Applicators: Shall have experiences of application of paint by airless spray at a minimum of two other sites at past.

1.3.2 Field Samples and Tests: The Government will take one-pint samples of paint at random from the products delivered to the job site and test them to verify that the products either conform to the referenced specifications or the approved substitution. Products which do not conform shall be removed from the job site and replaced with new products that conform to the referenced specification or the approved substitution.

#### 1.4 REGULATORY REQUIREMENTS:

1.4.1 Environmental Protection: In addition to requirements specified elsewhere for environmental protection, the Contractor shall provide coating materials that conform to the restrictions of the Japanese Air Pollution Control Act regional jurisdiction. Notify the Contracting Officer of any paint specified herein which fails to conform to the Air Quality Management District Rules for the location of the project. In localities where the specified coating or paint is prohibited, the Contracting Officer may direct the substitution of the acceptable coating systems.

1.4.2 Lead Content: Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.4.3 Chromate Content: Do not use coatings containing zinc-chromate or strontium-chromate.

1.4.4 Asbestos Content: Materials shall not contain asbestos.

1.4.5 Mercury Content: Materials shall not contain mercury or mercury compounds.

1.4.6 Toluene and Crystalline Silica: Materials shall be low toluene and crystalline silica free.

1.5 DELIVERY AND STORAGE: Deliver materials in sealed, labeled containers bearing the manufacturer's name, brand designation, specification number, batch number, color, and date of manufacture. Restrict storage and mixing of materials to locations designated by the Contracting Officer.

1.6 SAFETY METHODS: Apply coating materials using safety methods and equipment in accordance with the following:



1.6.1 Safety Methods Used During Coating Application: Comply with the requirements of SSPC-PA Guide 3.

1.6.2 Toxic Materials: To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

a. The chemical manufacturer when using mineral spirits, or other chemicals. Use impermeable gloves, chemical goggles or faceshield, and other recommended protective clothing and equipment to avoid exposure of skin, eyes, and respiratory system. Conduct work in a manner to minimize exposure of building occupants and the general public.

b. 29 CFR 1910.1000.

c. The Japanese Labor, Safety, and Sanitation Law.

d. Japanese Regulation of Organic Solvent Toxication Prevention

e. Manufacturer's Material Safety Data Sheets (MSDS).

1.7 ENVIRONMENTAL CONDITIONS: In accordance with JASS 18.

1.8 COLOR SELECTION: Colors of finish coats shall be as indicated or specified. Where not indicated or specified, colors and type of paint (such as gloss, semi-gloss, etc.) shall be selected by the Contracting Officer from color samples of JPMA.

## PART 2 - PRODUCTS

### 2.1 MATERIALS:

2.1.1 Anticorrosive Paint: JIS K 5629.

2.1.2 Ready Mixed Paint (Synthetic Resin Type): JIS K 5516, Type 1.

2.1.3 Vinyl Chloride Resin Enamel: JIS K 5582.

2.1.4 Vinyl Chloride Resin Primer: JIS K 5583.

## PART 3 - EXECUTION

3.1 PROTECTION OF AREAS AND SPACES: Prior to surface preparation and coating applications, remove, mask, or otherwise protect, hardware, hardware accessories, machined surfaces, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, workmen skilled in the trades involved shall reinstall removed items. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 SURFACE PREPARATION: Before application of painting, remove dirt, splinters, loose particles, grease, oil, disintegrated coatings, and other substances deleterious to coating performance and repair surface for coating preparation in accordance with JASS 18, unless otherwise specified hereinafter.

3.2.1 New Galvanized Steel(GS) Surface: Solvent clean in accordance with SSPC-SP 1 to remove oil and grease.

3.2.2 New and Existing Wood Surface: Remove dust and other deleterious substances using with brush, lightly sand to roughen the entire area using with sand paper, and perform cosmetic repair of minor defects, in accordance with JASS 18, Para 5.3, "Surface Preparation", Type 2. Existing paint on wood surface contains lead. Handling of LBP which is encountered during surface preparation shall conform to Section 13283, "Removal and Disposal of Lead-containing Paint".

3.2.3 Existing Polyvinyl Chloride(PVC) Surface: Solvent clean in accordance with the coating manufacturer.

### 3.3 APPLICATION:

3.3.1 GS Surface: Apply anticorrosive paint, JIS K 5629, in the rate of 0.10 kg/m<sup>2</sup>, and two coats of top coat, synthetic resin type ready mixed paint, JIS K 5516, in the rate of 0.08 kg/m<sup>2</sup> per one coat in accordance with JASS 18, Para 3.4, "Synthetic Resin Type Ready Mixed Paint", Type B.

3.3.2 Wood Surface: Apply one coat of under coat, in the rate of 0.10 kg/m<sup>2</sup>, and two coats of top coat, synthetic resin type ready mixed paint, JIS K 5516, in the rate of 0.08 kg/m<sup>2</sup> per one coat, in accordance with JASS 18, Para 5.10, "Synthetic Resin Type Ready Mixed Paint", Type B.

3.3.3 PVC Surface: Apply primer, JIS K 5583, in accordance with the coating manufacturer, and two coats of vinyl chloride resin enamel type paint, JIS K 5582, in the rate of 0.12 kg/m<sup>2</sup> per one coat.

3.4 INSPECTION AND ACCEPTANCE: In addition to meeting the previously specified requirements, demonstrate the mobility of moving components, including but not limited to swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of the coatings have elapsed and prior to invoicing for final payment.

\*\*\* END OF SECTION \*\*\*

DIVISION 13

SPECIAL CONSTRUCTION

SECTION 13283

REMOVAL AND DISPOSAL OF LEAD-CONTAINING PAINT

PART 1 GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred within the text by the basic designation only.

1.1.1 American National Standards Institute (ANSI):

ANSI Z88.2 (1992) Respiratory Protection

1.1.2 Code of Federal Regulations (CFR):

29 CFR 1926.21	Safety Training and Education
29 CFR 1926.55	Gases, Vapors, Fumes, Dusts, and Mists
29 CFR 1926.59	Hazard Communication
29 CFR 1926.62	Lead Exposure in Construction
29 CFR 1926.65	Hazardous Waste Operations and Emergency Response
29 CFR 1910.134	Respiratory Protection
40 CFR 745	Lead; Requirements for Lead-Based Paint Activities
49 CFR 172	Hazardous Materials, Tables, and Hazardous Materials Communications Regulations
49 CFR 178	Shipping Container Specification

1.1.3 Underwriters Laboratories Inc. (UL):

UL 586 (1990) High-Efficiency, Particulate, Air Filter Units

1.1.4 DOD Japan Environmental Governing Standards (JEGS), accomplished by US Forces Japan, American Embassy, and Japanese Government Agencies, October 2001, Version 1.1 (Revised: June 2002).

1.2 DEFINITIONS:

1.2.1 Lead: Metallic lead, inorganic lead compounds, and organic lead soaps.

1.2.2 Lead Based Paint (LBP): Paint or other surface coating that contains lead in excess of 1.0 milligrams per centimeter squared or 0.5 percent by weight.

1.2.3 Competent Person (CP): As used in this section, refers to a person employed by the Contractor who is trained in the recognition and control of lead hazards in accordance with Environmental Protection Agency (EPA).

1.2.4 High Efficiency Particulate Air (HEPA) Filter Equipment: HEPA filtered vacuuming equipment with a UL 586 filter system capable of collecting and retaining lead-contaminated paint dust. A high efficiency particulate filter means 99.97 percent efficient against 0.3 micron or larger size particles.

1.2.5 Lead Control Area : An enclosed area or structure, constructed as a temporary containment equipped with HEPA filtered local exhaust, which prevents the spread of lead dust, paint chips, or debris existing as a condition of lead based paint removal operations. The lead control area is also isolated by physical boundaries to prevent unauthorized entry of personnel.

### 1.3 QUALITY ASSURANCE:

1.3.1 Medical Examinations: Before exposure to lead-contaminated dust, provide workers with a comprehensive medical examination as required by 29 CFR 1926.62 and 29 CFR 1910.134. The examination will not be required if adequate records show that employees have been examined as required by 29 CFR 1926.62 within the last year.

1.3.1.1 Medical Records: Maintain complete and accurate medical records of employees for a period of at least 30 years or for the duration of employment plus 30 years, whichever is longer.

1.3.1.2 Medical Surveillance: Provide medical surveillance to all personnel exposed to lead as indicated in 29 CFR 1926.62.

#### 1.3.2 Competent Person (CP) Responsibilities:

a. Certify training as meeting all federal, and local requirements

b. Review and approve lead based paint removal plan for conformance to the applicable referenced standards.

c. Continuously inspect lead based paint removal work for conformance with the approved plan.

d. Ensure work is performed in strict accordance with specifications at all times.

e. Control work to prevent hazardous exposure to human beings and to the environment at all times.

f. Certify the conditions of the work as called for elsewhere in this specification.

1.3.3 Training: Train each employee performing paint removal, disposal, and air sampling operations prior to the time of initial job assignment and annually thereafter, in accordance with 29 CFR 1926.21, 29 CFR 1926.62, and local regulations.

1.3.3.1 Training Certification: Submit a certificate for each employee, signed and dated by the training source approved by EPA, stating that the employee has received the required lead training.

1.3.4 Respiratory Protection Program:

a. Furnish each employee required to wear a negative pressure respirator or other appropriate type with a respirator fit test at the time of initial fitting and at least every one(1) year thereafter as required by 29 CFR 1926.62.

b. Establish and implement a respiratory protection program as required by ANSI Z88.2, 29 CFR 1910.134, 29 CFR 1926.62, and 29 CFR 1926.55.

1.3.5 Hazard Communication Program: Establish and implement a Hazard Communication Program as required by 29 CFR 1926.59.

1.3.6 Hazardous Waste Management: The Hazardous Waste Management Plan shall comply with applicable requirements of federal, and local hazardous waste regulations and address:

a. Identification and classification of hazardous wastes associated with the work.

b. Estimated quantities of wastes to be generated and disposed of.

c. Names and qualifications of each contractor that will be transporting, storing, treating, and disposing of the wastes. Include the facility location and a 24-hour point of contact. Furnish two(2) copies of local hazardous waste permit applications.

d. Names and qualifications (experience and training) of personnel who will be working on-site with hazardous wastes.

e. List of waste handling equipment to be used in performing the work, to include cleaning, volume reduction, and transport equipment.

f. Spill prevention, containment, and cleanup contingency measures including a health and safety plan to be implemented in accordance with 29 CFR 1926.65.

g. Work plan and schedule for waste containment, removal and disposal. Wastes shall be cleaned up and containerized daily.

h. Cost for hazardous waste disposal according to this plan.

1.3.7 Safety and Health Compliance: In addition to the detailed requirements of this specification, comply with laws, ordinances, rules, and regulations of federal, and local authorities regarding removing, handling, storing, transporting, and disposing of lead waste materials. Comply with the applicable requirements of the current issue of 29 CFR 1926.62. Submit matters regarding interpretation of standards to the Contracting Officer for resolution before starting work. Where specification requirements and the referenced documents vary, the most stringent requirement shall apply.

1.3.8 Pre-Construction Conference: Along with the CP, meet with the Contracting Officer to discuss in detail the hazardous waste management plan and the lead based paint removal plan, including work procedures and precautions for the removal plan.

1.4 DESCRIPTION OF WORK: Existing paint on wood framing to be repainted, and door and window frame, galvanized steel(GS) flashing to be removed contains lead. Handling of the lead-based paint shall be as specified hereinafter.

1.5 SUBMITTALS: Submit the following in accordance with Section 01330, "Submittal Procedures".

1.5.1 SD-02, Manufacturer's Catalog Data:

- a. Vacuum filters
- b. Respirators

1.5.2 SD-08, Statements:

- a. Qualifications of CP
- b. Lead based paint removal plan including CP approval (signature, date, and certification number)
- c. Rental equipment notification
- d. Respiratory protection program
- e. Hazard communication program

- f. Hazardous waste management plan
- g. Environmental Protection Agency(EPA) approved hazardous waste treatment or disposal facility for lead disposal

1.5.2.1 Qualifications of CP: Submit name, address, and telephone number of the CP selected to perform responsibilities specified in paragraph titled "Competent Person (CP) Responsibilities." Provide previous experience of the CP. Submit proper documentation that the CP is trained and licensed in accordance with EPA.

1.5.2.2 Lead Based Paint Removal Plan (LBPRP): Submit a detailed job-specific plan of the work procedures to be used in the removal of LBP. The plan shall include a sketch showing the location, size, and details of lead control areas. Include in the plan, eating, drinking, smoking and sanitary procedures, interface of trades, sequencing of lead related work, collected paint debris disposal plan, respirators, personal protective equipment, and a detailed description of the method of containment of the operation to ensure that airborne lead concentrations of 30 micrograms per cubic meter of air and baseline lead dust concentrations are not reached or exceeded outside of the lead control area.

1.5.3 SD-13, Certificates:

- a. Vacuum filters

1.5.4 SD-18, Records:

- a. Completed and signed hazardous waste manifest from treatment or disposal facility
- b. Certification of medical examinations
- c. Employee training certification

1.6 REMOVAL:

1.6.1 Title to Materials: Materials resulting from demolition work, except as specified otherwise, shall become the property of the Contractor and shall be disposed of in accordance with Section 02220, "Site Demolition," except as specified herein.

1.7 EQUIPMENT:

1.7.1 Respirators:

1.7.1.1 Respirators: Furnish appropriate respirators approved by the National Institute for Occupational Safety and Health (NIOSH) for use in atmospheres containing lead dust. Respirators shall comply with the requirements of 29 CFR 1910.134.



1.7.2 Special Protective Clothing: Furnish personnel who will be exposed to lead-contaminated dust with proper disposable protective whole body clothing, head covering, gloves, foot coverings, and faceshield or goggle as required by 29 CFR 1926.62. Furnish proper disposable plastic or rubber gloves to protect hands. Reduce the level of protection only after obtaining approval from the CP.

1.7.3 Rental Equipment Notification: If rental equipment is to be used during lead based paint handling and disposal, notify the rental agency in writing concerning the intended use of the equipment. Furnish a copy of the written notification to the Contracting Officer.

1.7.4 Vacuum Filters: UL 586 labeled HEPA filters.

1.7.5 Equipment for Government Personnel: Furnish the Contracting Officer with two(2) complete sets of personal protective equipment (PPE) daily, as required herein, for entry into and inspection of the paint removal work within the lead controlled area. Personal protective equipment shall include disposable whole body covering, including appropriate foot, head, and hand protection. PPE shall remain the property of the Contractor. Respiratory protection for the Contracting Officer will be provided by the Government.

## PART 2 - PRODUCTS

Not used.

## PART 3 - EXECUTION

### 3.1 PROTECTION:

3.1.1 Notification: Notify the Contracting Officer 20 days prior to the start of any paint removal work.

3.1.2 Protection of Existing Work to Remain: Perform LBP removal work without damage or contamination of adjacent areas. Where existing work is damaged or contaminated, restore work to its original condition or better.

3.1.3 Lead Control Area Requirements: Establish a lead control area where LBP removal operations will be performed with 3-m rope off area and provide warning sign. Put down ground covering with vinyl sheet with edge inside the lead control area.

3.1.3.1 Notification to the Building Residents: Prior to the LBP removal work, the Contracting Officer will notify the building residents not to enter the control area.

3.1.4 Personnel Protection: Personnel shall wear and use protective clothing and equipment as specified herein. Eating, smoking, or drinking or application of cosmetics is not permitted in the lead control area. No one will be permitted in the lead control area unless they have been appropriately trained and provided with protective equipment.

3.1.5 Warning Signs: Provide warning signs at approaches to lead control areas. Locate signs at such a distance that personnel may read the sign and take the necessary precautions before entering the area. Signs shall comply with the requirements of 29 CFR 1926.62.

3.2 WORK PROCEDURES : Perform removal of LBP in accordance with approved lead based paint removal plan. Use procedures and equipment required to limit occupational and environmental exposure to lead when lead based paint is removed in accordance with 29 CFR 1926.62, except as specified herein. Dispose of removed paint chips and associated waste in compliance with EPA, federal, and local requirements.

3.2.1 Personnel Exiting Procedures: Whenever personnel exit the lead-controlled area, they shall perform the following procedures and shall not leave the work place wearing any clothing or equipment worn during the work day:

- a. Vacuum themselves off.
- b. Remove protective clothing in the decon area, place them in an approved impermeable disposal bag, and change to clean clothes.

#### 3.2.2 Lead Based Paint Removal:

3.2.2.1 Wood Framing to be Repainted: Remove loose and deteriorated LBP with hand tool as specified in Section 09900, "Paints and Coatings" and collect paint chips for disposal in accordance with EPA, and local requirements. Take whatever precautions necessary to minimize damage to the underlying substrate.

3.2.2.2 Wood Door and Window Frame and GS Flashing: Remove wood door and window frame and GS flashing and collect paint chips for disposal in accordance with EPA, and local requirements.

#### 3.2.3 Cleanup and Disposal:

3.2.3.1 Cleanup: Maintain surfaces of the lead control area free of accumulations of paint chips and dust. Restrict the spread of dust and debris; keep waste from being distributed over the work area. Do not dry sweep or use compressed air to clean up the area. At the end of each shift and when the paint removal operation has been completed, clean the area of visible lead paint contamination by vacuuming with a HEPA filtered vacuum cleaner, wet mopping the area and wet wiping the area as indicated by the CP. Reclean areas showing dust or residual paint chips or debris. After visible dust, chips and debris is removed, wet wipe and HEPA vacuum all surfaces in the work area. If adjacent areas become contaminated at any time during the work, clean, visually inspect, and then wipe sample all contaminated areas. The CP shall then certify in writing that the area has been cleaned of lead contamination before restarting work.

3.2.3.2 Certification: The CP shall certify in writing that the respiratory protection used for the employees was adequate; the work procedures were performed in accordance with 29 CFR 1926.62 and 40 CFR 745; and that there were no visible accumulations of lead based paint and dust left in the work site. Do not remove the lead control area and warning signs prior to the Contracting Officer's acknowledgement of receipt of the CP certification.

3.2.3.3 Disposal:

a. Collect lead-contaminated waste, scrap, debris, bags, containers, equipment, and lead-contaminated clothing which may produce airborne concentrations of lead particles. Label the containers in accordance with 29 CFR 1926.62 and JEGS. Dispose of lead-contaminated waste material at a local, prefectural, and GOJ environmental regulatory agencies-approved hazardous waste treatment, storage, or disposal facility off Government property.

b. Store waste materials in U.S. Department of Transportation (49 CFR 178) approved 208 liter (55 gallon) drums. Properly label each drum to identify the type of waste (49 CFR 172) and the date the drum was filled. The Contracting Officer or an authorized representative will assign an area for interim storage of waste-containing drums. Do not store hazardous waste drums in interim storage longer than 90 calendar days from the date affixed to each drum.

c. Handle, store, transport, and dispose lead or lead-contaminated waste in accordance with JEGS. Comply with land disposal restriction notification requirements as required by JEGS.

3.2.4 Disposal Documentation: Submit written evidence that the hazardous waste treatment, storage, or disposal facility (TSD) is approved for lead disposal by the local, prefectural, or GOJ

environmental regulatory agencies. Submit one copy of the completed manifest, signed and dated by the initial transporter.

3.2.5 Payment for Hazardous Waste: Payment for disposal of hazardous waste will not be made until a signed copy of the manifest from the treatment or disposal facility certifying the amount of lead-containing materials delivered is returned and a copy is furnished to the Government.

\*\*\* END OF SECTION \*\*\*

DIVISION 16

ELECTRICAL

SECTION 16050

BASIC ELECTRICAL MATERIALS AND METHODS

PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1.1.1 American National Standards Institute (ANSI):

ANSI C2                      2002 National Electrical Safety Code

1.1.2 Institute of Electrical and Electronics Engineers (IEEE):

IEEE 100                    1996 Dictionary of Electrical and Electronics  
Terms

1.1.3 National Electrical Manufacturers Association (NEMA):

NEMA ICS 6                1996 Enclosures for Industrial Controls and  
Systems

1.1.4 National Fire Protection Association (NFPA):

NFPA 70                    2002 National Electrical Code

1.2 RELATED REQUIREMENTS: This section applies to all sections of Division 16, "Electrical," of this project specification unless specified otherwise in the individual sections.

1.3 DEFINITIONS:

- a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE 100.
- b. The technical sections referred to herein are those specification sections that describe products, installation

procedures, and equipment operations and that refer to this section for detailed description of submittal types.

- c. The technical paragraphs referred to herein are those paragraphs in PART 2 -PRODUCTS and PART 3 -EXECUTION of the technical sections that describe products, systems, installation procedures, equipment, and test methods.

1.4 SUBMITTALS: Submittals shall be specified in Section 01330, "Submittal Procedures", unless otherwise specified hereinafter.

1.5 QUALITY ASSURANCE:

1.5.1 Material and Equipment Qualifications: Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.

1.5.2 Regulatory Requirements: Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70.

1.5.3 Alternative Qualifications: Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.4 Manufacturer's Nameplate: Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable. Letter for manufacturer's nameplate shall be written in English and Japanese.

1.5.5 Modification of References: In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer.

1.6 ELECTRICAL REQUIREMENTS: Electrical installations shall conform to ANSI C2, NFPA 70, and requirements specified herein.

1.6.1 Wiring and Conduit: Provide internal wiring for components of packaged equipment as an integral part of the equipment. Provide power wiring and conduit for field-installed equipment under Section 16402, "Electrical Distribution System." Wiring and conduit shall be provided under, and conform to the requirements of the section specifying the associated equipment.

1.7 PCB, LEAD AND ASBESTOS CONTAINING MATERIAL: Use of PCB, Lead and Asbestos containing material and devices shall not be permitted.

1.8 ECOLOGICAL WIRES AND CABLES: Eco wires and cables which are composed of only environment-friendly and ecologically sound materials that, when burnt, release minimum smoke and emit no harmful gases including dioxins or that are recyclable. All eco wires and cables shall conform to each JCS standards specified in each technical Sections in Division 16.

## PART 2 - PRODUCTS

Not used.

## PART 3 - EXECUTION

### 3.1 PAINTING OF EQUIPMENT:

3.1.1 Factory Applied: Electrical equipment shall have factory-applied painting systems which shall, as a minimum, meet the requirements of NEMA ICS 6 corrosion-resistance test.

3.1.2 Field Applied: Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in Section 09900, "Paints and Coatings."

3.2 MOUNTING HEIGHTS OF ELECTRICAL EQUIPMENT AND MATERIALS: Unless otherwise indicated on drawings and specifications, the locations and heights where new equipment and materials shall be installed are at the Contractor's option.

\*\*\* END OF SECTION \*\*\*



## SECTION 16402

### ELECTRICAL DISTRIBUTION SYSTEM

#### PART 1 - GENERAL

1.1 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

##### 1.1.1 National Fire Protection Association (NFPA):

NFPA 70                      2002 National Electrical Code

##### 1.1.2 Japan Defense Facilities Administration Agency's Publication:

Japan Defense Facilities Administration Agency Electrical  
Construction Standard Specification ("Boheicho Denki Setsubi  
Kohji Kyohtsu Siyoh Sho")

##### 1.1.3 Japanese Industrial Standards (JIS):

C 0920-93	Test to Prove Protection against Ingress of Water for Electrical Equipment
C 2336-99	Pressure-Sensitive Adhesive Polyvinyl Chloride Tapes for Electrical Insulation
C 2805-91	Crimp-Type Terminal Lugs for Copper Conductors
C 2806-91	Non-Insulated Crimp-Style Connecting Sleeves for Copper Conductor
C 2810-95	General Rules on Non-separable Type Wire Connectors for Interior Wiring
G 3101-95	Rolled Steel for General Structure

##### 1.1.4 Japanese Architectural Standard Specification:

JASS 11-68                  Carpentry

1.2 RELATED REQUIREMENTS: Section 16050, "Basic Electrical Materials and Methods," applies to this section with additions and modifications specified herein.

1.3 QUALITY ASSURANCE: In each standard referred to herein, consider the advisory provisions to be mandatory, as though the word "shall" has been substituted for "should" wherever it appears. Interpret references in these standards to "authority having jurisdiction," or words of similar meaning, to mean Contracting Officer.

## PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT: All materials, equipment, and devices shall, as a minimum, meet the requirements of JIS where JIS Standards are established for those items, and the requirements of NFPA 70. All items shall be new unless specified or indicated otherwise.

2.2 PULL BOX: Pull box shall conform to the Standard, "Japan Defense Facilities Administration Agency Electrical Construction Standard Specification". Weather-proof box shall conform to JIS C 0920 and exposed screws to weather shall be non-corrosive material. Cabinet shall be of sheet steel.

### 2.3 WIRES, CABLES AND TAPES:

2.3.1 Wires and Cables: Wires and cables shall meet applicable requirements of NFPA 70 and JIS for type of insulation, jacket, and conductor specified or indicated. All conductors shall be copper. Conductor sizes are based on copper. Wires and cables manufactured more than 12 months prior to date of delivery to site shall not be used.

2.3.1.1 TV Cable: Shall be same dimension and electrical characteristics as existing cable. BS cable shall have polyethylene-insulated and inflammable-polyethylene sheathed cable.

2.3.2 Insulation Tape: JIS C 2336.

2.4 SPLICES AND TERMINATION COMPONENTS: JIS C 2810, C 2806, and C 2805. Provide solderless terminal lugs on all conductors.

2.5 BS ANTENNA SUPPORTS PLATE AND BOLTS: Shall be products recommended by the BS antenna manufacturer.

2.6 CONDUIT AND CABLE SUPPORT: Shall conform to JIS G 3101, type SS 400.

2.7 WOODEN PLATE: Shall be sawn lumber described in JASS.

### PART 3 - EXECUTION



3.1 INSTALLATION: Electrical installations shall conform to requirements of NFPA 70 and to requirements specified herein.

3.2 RESTORATION: Unless otherwise indicated, all existing objects which interfere with new work shall be removed temporary and reinstalled upon completion of new work.

3.3 PAINTING AND FINISHING: Field-applied paint on exposed metal surfaces of existing and new electrical equipment, wiring devices and pull box as indicated. Painting work shall be in accordance with the requirements specified in Section 09900, "Paints and Coatings."

\*\*\* END OF SECTION \*\*\*





LEGEND :

PROJECT BLDGS.	BLDGS.
OTHER BLDGS. (NIC)	

LOCATION MAP : (HOUSING AREA)

SCALE : 1/2000

GRAPHIC SCALE :



1/2000  
IF OUTSIDE APPROVED, IN 1:1000  
HAWN 347 427 USE GRAPHIC SCALE

BUILDING SCHEDULE LIST:

BUILDING NUMBERS	BUILDING TYPE	REMARKS	BUILDING NUMBER	BUILDING TYPE	REMARKS
628	B-2		681	B-10	
660	B-10		684	T-2	
664	B-10		686	A-10	
666	T-4		687	A-11	
673	T-4		688	A-10	
674	A-2		689	T-13	
677	A-10		697	A-1	
678	T-4		698	B-2	

WM # 87512




DEPARTMENT OF THE ARMY  
OICC FAR EAST  
HOUSING ACTIVITY CIVIL ENGINEER, COMMANDER U.S. MARINE FORCE, JAPAN  
REPLACE SIDING,  
NEGISHI  
LOCATION MAP AND SCHEDULE LIST

SEAL AREA




PUBLIC WORKS CENTER, JAPAN  
DESIGN & ENGINEERING DEPT.  
SUBMITTED BY TITLE DATE  
FUNCTIONAL APPROVAL DATE  
APPROVED DATE  
BY FOR COMMANDER NAVFAC

PHC/OICC/ROICC REVIEW/SUPV.  
ACC DIR: ELECT:  
DISC/DNR: CAIL:  
PDE/EC: RAC PROT:  
ARCH: V-C:  
STRUCT: ROICC:  
MECH: LTR:

REVISIONS  
PREP. BY DATE APPROVED



FLOOR PLAN A-1 OR A-1r  
BLDG NO 687(\*) & 697(\*)







FLOOR PLAN A-2  
BLDG NO 674(\*)

GEOMETRIC SCALE: 1/100  
1000 2 1500 5000 10000 (MM)

IF DIMENSIONED IS LESS THAN 1/4" X 1/4" USE DIMENSION SCALE

DEPARTMENT OF THE NAVY CIVIL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN HOUSING ACTIVITY CIVIL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN REPLACE SIDING, NEGISHI PLANS AND ELEVATIONS		PUBLIC WORKS CENTER, JAPAN DESIGN & ENGINEERING DEPT. DESIGNED BY: [ ] CHECKED BY: [ ] SUBMITTED BY: [ ] DATE: [ ] APPROVED: [ ] DATE: [ ] FOR COMMANDER, NAJAF		PWC/DOCE/ROICE REVIEW/SUPV. AGO DIR: [ ] DISCHDR: [ ] PDE/ENG: [ ] ARCH: [ ] STRUCT: [ ] MECH: [ ]		ELECT: [ ] CIVIL: [ ] FIRE PRO: [ ] V-E: [ ] ROICE: [ ] LTR: [ ]		REVISIONS PREP. BY: [ ] DATE: [ ] APPROVED: [ ]	
--	--	---	--	--	--	---	--	--	--



FLOOR PLAN A-10  
BIDS NO 877(G), 886(G) & 888(G)

GRAPHIC SCALE: 1/100  
1000 0 1000 5000 10000 (MM)

(\*)-REPLACE EXIST PVC CUTTER & DOWNSPOUT W/ NEW


IF DIVISION BORDER IS LESS THAN 1/16" USE GRAPHIC SCALE

WD # B7512

DEPARTMENT OF THE NAVY OIC: FAR EAST HOUSING ACTIVITY CHL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN REPLACE SIDING, NEGISHI PLANS AND ELEVATIONS				PUBLIC WORKS CENTER, JAPAN DESIGN & ENGINEERING DEPT. DESIGNED BY: T. S. LEE SUBMITTED BY: T. S. LEE FUNCTIONAL APPROVAL: DATE: _____ APPROVED: DATE: _____ FOR THE COMMANDER, NAVFAC				PWC/OICC/ROICC REVIEW/SMPF: ACC DIR: ELECT: DISC/DIR: CIVIL: PDL/DIR: FIRE PROT: ARCH: V-E: STRUCT: ROICC: MECH:				REVISIONS PREP BY: DATE: APPROVED:			
---	--	--	--	---	--	--	--	--	--	--	--	---------------------------------------	--	--	--









C ELEVATION :  
SCALE: 7/100

D ELEVATION :  
SCALE: 7/100



A ELEVATION :  
SCALE: 7/100

B ELEVATION :  
SCALE: 7/100



FLOOR PLAN B-2  
BLDG NO 528 & 598

GRAPHIC SCALE : 1/100






IF DIVISION BORDER IS LESS THAN 3/16" USE GRAPHIC SCALE

WD # 07SL2

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND OICC FAR EAST THUSUKA, JAPAN HOUSING ACTIVITY CIVIL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN REPLACE SIDING, NEGISHI PLAN AND ELEVATIONS		PUBLIC WORKS CENTER JAPAN DESIGN & ENGINEERING DEPT. DESIGNED BY SUBMITTED BY PLANNING APPROVAL APPROVED DATE FOR COMMANDER, NAVFAC		PNC/OICC/ROICC REVIEW/SUPV. ACC DIR DIS/DIR PDE/EC ARCH STRUCT. MECH. ELEC. CIVIL FIRE PROT. V-E ROICC		REVISIONS PREP. BY DATE APPROVED	
--	--	--	--	---	--	---	--






FLOOR PLAN T-4  
BLDG NO 666, 673 & 678(\*)


(\*)-REPLACE EXST PVC GUTTER & DOWNSPOUT W/ NEW

03	DRAWING SCALE: 1/8" = 1'-0"	DATE: 11/1/78	SHEET: 8 OF 15	AS	DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND OICC FAR EAST YOKOSUKA, JAPAN HOUSING ACTIVITY CIVIL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN REPLACE SIDING, NEGISHI PLAN AND ELEVATIONS	PUBLIC WORKS CENTER, JAPAN DESIGN & ENGINEERING DEPT. DESIGNED BY: [ ] CHECKED BY: [ ] SUBMITTED BY: [ ] TITLE: [ ] DATE: [ ] FUNCTIONAL APPROVAL: [ ] GATE: [ ] APPROVED: [ ] DATE: [ ] FOR: [ ]	PWC/OICC/PD/C: [ ] REVIEW/SUPV: [ ] ADD DIR: [ ] ELECT: [ ] DESIGNOR: [ ] CIVIL: [ ] FIRE PROT: [ ] V-E: [ ] STRUCT: [ ] PD/C: [ ] MECH: [ ]	11A DESCRIPTION: [ ] REVISIONS: [ ]	PREP. BY: [ ] DATE: [ ] APPROVED: [ ]
					CODE: [ ] NO. 00001 DRAWING SCALE: 1/8" = 1'-0" CONSTRUCTION: [ ] NO. 00001 DATE: 11/1/78 SHEET: 8 OF 15				







GABLE SECTION FOR SINGLE STORY BLDG:  
SCALE: 1/20



EAVES SECTION FOR SINGLE STORY BLDG:  
SCALE: 1/20















EAVES SECTION FOR TWO-STORY BLDG:  
SCALE: 1/20



GABLE SECTION FOR TWO-STORY BLDG:  
SCALE: 1/20

GRAPHIC SCALE:  
0 500 1000 2000 3000 (mm)  
1/20

DEPARTMENT OF THE NAVY CIVIL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN HOUSING ACTIVITY CIVIL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN REPLACE SIDING, NEGISHI TYPICAL SECTIONS		PUBLIC WORKS CENTER, JAPAN DESIGN & ENGINEERING DEPT. DESIGNED BY: DATE: 1/78 SUBMITTED BY: DATE: 1/78 FUNCTIONAL APPROVAL: DATE: 1/78 APPROVED: DATE: 1/78 DESIGNED FOR: COMMANDER, NAVFAC		PHC/DOCC/ROCC REVIEW/SUPV. AGO DIR: ELECT: DIS/DIR: CAIL: PDE/EC: FIRE PROT: ARCH: V-E: STRUCT: ROICC: MECH: LTR		REVISIONS PREP. BY: DATE: APPROVED:	
--	--	---	--	--	--	--	--



TYPICAL DETAILS (1)  
SCALE: 1/5

GRAPHIC SCALES:  
1/5  
1/10






DEPARTMENT OF THE NAVY  
NAVAL FACILITIES ENGINEERING COMMAND  
CHIEF, FAR EAST  
REPLACE SIDING,  
NEGISHI  
TYPICAL DETAILS (1)

PUBLIC WORKS CENTER, JAPAN  
DESIGN & ENGINEERING DEPT.  
DES: [ ]  
SUMMITED BY: [ ]  
FUNCTIONAL APPROVAL: [ ]  
APPROVED: [ ]  
FOR COMMANDER, NAVFAC

PHC/OC/PROCC REVIEW/SUPP.  
ELECT: [ ]  
CIVIL: [ ]  
FRC PROJ: [ ]  
V-E: [ ]  
ROCC: [ ]  
LTH: [ ]  
DESCRIPTION: [ ]  
PREP BY: [ ]  
DATE: [ ]  
APPROVED: [ ]

REVISIONS



IF OUTSIDE BORDER IS LESS  
THAN 34"x22" USE GRAPHIC SCALE

# GENERAL DESCRIPTION OF WORK:

1. LOOSEN EXISTING ELECTRICAL MATERIALS TEMPORARILY WHEN RELOCATING. MATERIALS TO BE REMOVED AND REINSTALLED WITH NEW SUPPORT PLATES AFTER ARCHITECTURAL WORK HAS BEEN COMPLETED AS SHOWN.
2. REPLACE WOODEN PLATES WITH NEW ONES AS SHOWN.
3. PARTIAL EXPOSED PULL BOXES, BREAKER BOXES, CONDUIT PIPES, STEEL ANGLES, SUPPORTS, WOODEN PLATE, FITTINGS AS SHOWN, RELOCATE EXISTING BS ANTENNA AND PROVIDE NEW STEEL SUPPORT AND CABLE AS SHOWN. (BUDG 684 ONLY)
4. REPLACE PULL BOXES WITH NEW ONES AS SHOWN. (BUDG 673 ONLY)

## NOTES:

1. FOR APPLICABLE NOTES, SEE DWG A1.
2. THE QUANTITIES ON DRAWINGS ARE FOR BIDDING PURPOSE ONLY.
3. TV PROTECTORS, SPLITTERS AND CABLES WHICH NOT USED NOW SHALL BE ALSO REINSTALLED.
4. THE WALL PENETRATION PORTION FOR TV AND TEL CABLES SHALL BE PREPARED SLEEVE AND WEATHERPROOFING PROCESSING.
5. REINSTALLED TV AND TEL CABLE SHALL BE TIED TO THE NEW WALL COLLECTIVELY TWO OR MORE CABLES SAID TO THE EXISTING WALL AND SHALL BE BOUND EVERY 300MM AND FIXED EVERY 600MM AS SHOWN.

## LEGEND:


- ELEC OVERHEAD CABLE W/MESSENGER WIRE  
ELEC CONDUIT WIRING, EXPOSED  
PULL BOX, EXPOSED  
BREAKER BOX, EXPOSED  
PANELBOARD  
WALL UNMOUNTED TYPE LIGHTING FIXTURE, WEATHERPROOF TYPE  
DOOR BELL  
RECEP/PLC OUTLET, WEATHERPROOF TYPE  
TV OVERHEAD CABLE W/MESSENGER WIRE  
TV CABLE  
TV PROTECTOR & SPLITTER (UNUSED)  
TV SPLITTER(S)  
TEL OVERHEAD CABLE W/MESSENGER WIRE  
TEL CABLE  
TEL PROTECTORS  
TEL OUTLET  
GROUNDING SYSTEM  
BS ANTENNA W/POL & CABLE

## ABBREVIATIONS:

- APPROX ——— APPROXIMATELY  
ELEC ——— ELECTRICAL  
H ——— HEIGHT  
LT ——— LOT  
M ——— METERS  
O/H ——— OVERHEAD  
QTY ——— QUANTITY
- TEL ——— TELEPHONE  
TEMP ——— TEMPORARILY  
TYP ——— TYPICAL  
TV ——— TELEVISION  
W ——— WITH  
& ——— AND  
Ø ——— DIAMETER OR PHASE

# ELECTRICAL MATERIALS LIST:

CATEGORY	NO.	MATERIAL NAME	UNIT	BLOC NO., TYPE & QTY																SCOPE OF WORK	REMARKS
				628	630	664	666	673	674	677	678	681	684	686	687	688	689	697	698		
ELEC	1	O/H WIRING SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	LOOSEN	RELOCATE
	2	PULL BOX (1)	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	3	PULL BOX (2)	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	4	BREAKER BOX	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	5	WOODEN PLATE	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	6	CONDUIT WIRING	M	10	30	30	60	60	10	40	60	20	60	60	20	60	40	10	10	RELOCATE	RELOCATE
	7	CONDUIT SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	8	WALL LIGHT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	9	DOOR BELL	EA	2	4	4	8	8	2	4	8	4	8	4	2	4	8	2	2	RELOCATE	RELOCATE
TV	10	RECEP/PLC OUTLET	EA	2	2	2	4	6	1	2	4	2	5	2	1	2	4	1	1	RELOCATE	RELOCATE
	11	O/H TV CABLE SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	12	TV PROTECTOR & SPLITTER (UNUSED)	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	13	TV SPLITTER	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	14	TV CABLE	M	100	180	180	300	300	80	150	300	180	250	150	80	150	250	80	100	RELOCATE	RELOCATE
	15	CABLE SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	16	BS ANTENNA	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	17	O/H TEL CABLE SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	18	TEL PROTECTOR	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	19	WOODEN PLATE	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
TEL	20	CONDUIT WIRING	M	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	RELOCATE	RELOCATE
	21	TEL CABLE	M	60	120	120	200	200	50	60	200	120	200	60	50	60	200	50	60	RELOCATE	RELOCATE
	22	TEL CABLE SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	23	BS ANTENNA	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	24	O/H TEL CABLE SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	25	TEL PROTECTOR	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	26	WOODEN PLATE	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE
	27	CONDUIT WIRING	M	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	RELOCATE	RELOCATE
	28	TEL CABLE	M	60	120	120	200	200	50	60	200	120	200	60	50	60	200	50	60	RELOCATE	RELOCATE
	29	TEL CABLE SUPPORT	EA	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	RELOCATE	RELOCATE





THIS TYP DRAWING IS TWO FLOOR AND FOUR HOUSES/UNITS TYPE BUILDING. WIRING LEGEND AND ELEC MATERIAL QUANTITY AND INSTALLATION POSITIONS DIFFER FROM BUILDING TYPES.


GRAPHIC SCALE:  
1000 0 1000 2000  
1/100  
10000 IF ORIGINATOR PROPOSES 1/255  
THAN 3/4" USE GRAPHIC SCALE








DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND OICC FAR EAST REPAIR UNIT HOUSING ACTIVITY CIVIL ENGINEER, COMMANDER U.S. NAVAL FORCE, JAPAN NEGISHI SCOPE OF WORK & ELEC MATERIAL LIST		PUBLIC WORKS CENTER, JAPAN DESIGN & ENGINEERING DEPT DATE: 2000/08/01 SUBMITTED BY: [Signature] FUNCTIONAL APPROVAL: [Signature] APPROVED: [Signature] FOR THE COMMANDER, JAPANESE		PWC/OCC/ROCC REVIEW/SUPPLY ACC DIR: [Signature] DISCOM: [Signature] PDE/EC: [Signature] ARCH: [Signature] STRUCT: [Signature] MECH: [Signature]		REVISIONS PREP BY: [Signature] DATE: [Signature] APPROVED: [Signature]	
---	--	--	--	---	--	---	--





BLDG 673  
SCALE : 1/100





### GRAPHIC SCALE:

500 0 1000 2000 3000 4000 5000

1/40

IF OUTSIDE BORDER IS LESS THAN 34" x 22" USE GRAPHIC SCALE

[illegible]